

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(B&I4) R-3	WILL	390	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 60961				

SUMMARY OF QUANTITIES

LOCATION OF WORK: U.S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL / 20% STATE			100% SUNNYLAND SANITARY DIST.	80% FEDERAL / 20% STATE		100% MUNICIPALITY		80% FEDERAL / 20% STATE
				ROADWAY I000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	Y060	TRAFFIC SIGNALS Y031-1F	TRAINING Y080	CREST HILL Y030-1E	JOLIET	SAFETY SFTY-3N
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	12241	12241								
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1620	1620								
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	3322	3322								
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	49	49								
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	55	55								
X4023000	TEMPORARY ACCESS (ROAD)	EACH	18	18								
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	544	544								
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	185	185								
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	10029	10029								
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	2222	2222								
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	39459	39459								
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE IL-4.75, N50	TON	2090	2090								
X4409410	BITUMINOUS SURFACE REMOVAL, 2 1/4"	SQ FT	32105	32105								
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	17992			17992						
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	16	16								
X7240500	RELOCATE EXISTING SIGNS	EACH	4	4								
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	2118	2118								
60228500	MANHOLES, SPECIAL WITH SPECIAL FRAME AND CLOSED LID	EACH	14	14								
*61600317	UNIT DUCT, 2*6 XLP-USE, 1*6 ^{BASE} GROUND 1 1/2" POLYETHYLENE	FOOT	341								341	
XX003653	SPECIAL STRUCTURE SP-1	EACH	1	1								
X0325058	SPECIAL STRUCTURE SP-2	EACH	1	1								
X0325059	SPECIAL STRUCTURE SP-3	EACH	1	1								
X0325060	SPECIAL STRUCTURE SP-4	EACH	1	1								
X0325061	SPECIAL STRUCTURE SP-5	EACH	1	1								
X0325062	SPECIAL STRUCTURE SP-6	EACH	1	1								
X0325063	SPECIAL STRUCTURE SP-7	EACH	1	1								

L:\DOT\0006602\design\comps\Summaryof Quantities\SumQuan008.dgn

LEGEND:
 NON-PARTICIPATING WORK
 * SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 US ROUTE 30
 SHEET 8 OF 8
 SCALE: N/A
 DATE: 3/1/05
 DRAWN BY: AMB
 CHECKED BY: KDF/AMB