

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(B&I) R-3	WILL	390	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60961				

55021700 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
33	738 + 60	34	738 + 60	9	2.93
*39	741 + 10	33	738 + 60	250	0
40	741 + 10	39	741 + 10	9	1.626
46	744 + 00	47	744 + 69	69	27.462
115	776 + 95	114	776 + 95	6	1.422
146	790 + 00	140A	789 + 98	12	3.66
176	794 + 00	177	796 + 10	110	0
177	795 + 10	179	796 + 20	110	20.007
214A	811 + 20	215	811 + 20	19	14.155
214B	811 + 08	214A	811 + 20	10	7.45
225	816+32.7	224	814 + 30	204	40.596
TOTAL				808	119

55021800 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
15	725 + 75	13	725 + 29	66	64.35
85	756 + 40	84	756 + 40	10	1.368
83	756+40	82	756+40	9	1.4
114	776 + 95	117	778 + 10	115	120.52
117	778 + 10	119	779 + 00	90	87.75
119	779 + 00	122	779 + 40	40	51
122	779+40	125	780+40	100	86.6
156	788 + 66	153	14 + 14	124	84.816
158	32 + 34	156	788 + 66	78	53.352
179	796 + 20	182	797+ 40	120	0
182	797 + 40	183	798 + 15	75	23.541
183	798 + 15	186	798 + 80	65	0
186	798 + 80	187	799 + 80	100	24.87
187	799 + 80	188	800 + 50	70	12.94
223	813 + 26	HD WALL	813 + 20	9	0
224	814 + 30	223	813 + 26	105	0
TOTAL				1176	612

55021900 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
53	745 + 61	54	745 + 73	9	4.59
52	745 + 61	52A	745 + 61	24	18.312
TOTAL				33	23

55022000 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
2	720 + 90	1	720 + 40	95	27.9
BC	720 + 98	2	720 + 90	10	8.9
3A	720 + 98	3	720 + 40	74	110.9
BC	721 + 10	3A	720 + 98	12	0
6	721 + 54	HD WALL	721 + 49	12	15.528
14	725+30.9	14A	725+30.9	18	16.7
16A	725 + 47	13	725 + 29	10	9.68
19	726 + 75	16B	726 + 47	26	36.816
19	726 + 75	17	726 + 75	55	57.695
55	746 + 55	55A	746 + 21	21	1.528
12 X 3 BC	746 + 55	56A	746 + 50	10	7.64
56	746 + 55	55	746 + 55	6	2.18
62	747 + 82	55	746 + 55	124	0
102	764+37	103	765+21	84	14.7
103	765+21	104	765+99.7	79	16.2
125	780 + 40	128	782 + 35	195	172.77
128	782 + 35	130	783 + 00	65	54.99
130	783 + 00	131	783 + 50	50	42.3
131	783 + 50	133A	784 + 55	165	84.525
133A	784 + 55	136	787 + 00	246	248.214
148	790 + 15	140A	789 + 98	10	8
201	805 + 60	201A	806 + 15	55	0
TOTAL				1422	938

55022100 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 27"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
EXISTING	720 + 88	BC	720 + 80	10	0
TOTAL				10	0

55022200 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
218	812 + 76	HD WALL	812 + 97	30	0
TOTAL				30	0

55022400 STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
153	14 + 14	EXISTING	15 + 48	237	228.468
-	16+50	153A	16+50	8	0
153A	16+50	-	16+50	8	0
TOTAL				253	228

55034300 STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
63	748 + 96	62	747 + 82	114	34.668
67	749 + 15	63	748 + 96	19	5.88
68	750 + 00	67	749 + 15	85	47.04
68A	750 + 43	68	750 + 00	38	2.482
104	765 + 99.7	105	766 + 34	27	8.721
TOTAL				283	99

X0322033 STORM SEWERS (WATERMAIN REQUIREMENT) 12 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
20	727 + 60	20A	727 + 60	18	1.264
12C	499+00	12B	499+33	47	9.1
23	730 + 10	25	730 + 10	55	11.825
26	732 + 60	28	732 + 60	55	11.825
32	735 + 00	29	733 + 80	120	95.04
32	735 + 00	31	734 + 75	67	15.812
35	738 + 60	34	738 + 60	60	68.7
48	744 + 69	8X2 BOX	744 + 69	36	5.28
65	749 + 15	66	749 + 15	60	7.92
71	751 + 20	70	751 + 20	60	9.12
79	755 + 10	78	755 + 10	8	0.3
61	747 + 85	12X3 BOX	747 + 85	38	13
93	760 + 65	92	760 + 65	60	11.64
94	762 + 50	8' X 2' BC	762 + 50	41	24.08
100	764 + 37	101	764 + 37	45	6.84
TOTAL				770	292

X0322034 STORM SEWERS (WATERMAIN REQUIREMENT) 15 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
12A	724 + 33	12B	499+33.1	33	1.065
37	741 + 10	40	741 + 10	60	19.74
TOTAL				93	21

X0322035 STORM SEWERS (WATERMAIN REQUIREMENT) 18 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
16	725 + 75	15	725 + 75	23	1.586
76	752 + 80	75	752 + 80	60	16.86
84	756 + 40	83	756 + 40	60	24.48
TOTAL				143	43

X0322525 STORM SEWERS (WATERMAIN REQUIREMENT) 21 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
52A	745 + 61	53	745 + 61	40	33.6
51	745 + 61	52	745 + 61	8	1.526
TOTAL				48	35

X0322125 STORM SEWERS (WATERMAIN REQUIREMENT) 24 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
17A	726 + 75	17	726 + 75	23	1.854
56A	746 + 50	56	746 + 55	44	35.42
64	748 + 96	63	748 + 96	82	9.512
TOTAL				149	47

X0322127 STORM SEWERS (WATERMAIN REQUIREMENT) 30 INCH

STRUCTURE	STATION	STRUCTURE	STATION	LENGTH, LF	TRENCH BACKFILL, CY
217	812 + 70.18	216A	811 + 46	121	18.7
TOTAL				121	19

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**PROPOSED DRAINAGE
PIPE SCHEDULE**
US ROUTE 30
SHEET 8 OF 8



SCALE: VERT. NONE
HORIZ. NONE
DATE: 3/1/05
DRAWN BY: AMB
CHECKED BY: KDF