

93.3/STATE
6.7%
VILLAGE

93.3/STATE
6.7%
VILLAGE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A	BRIDGE SN 099-4648 STATE 100% X071-2A	RETAINING WALL SN 099-W012 STATE 100% Y007	TRAFFIC SIGNALS Y031-1F	OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1	
* A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12	12				
* A2002374	TREE, BETULA NIGRA (RIVER BIRCH), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	6	6				
* A2005116	TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER, BALLED AND BURLAPPED	EACH	24	24				
* A2005614	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	22	22				
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	36	36				
* C2000524	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 2' HEIGHT, BALLED AND BURLAPPED	EACH	10	10				
* C2012748	SHRUB, VIBURNUM PRUNIFOLIUM (BLACKHAW VIBURNUM), 4' HEIGHT, BALLED AND BURLAPPED	EACH	167	167				
* C2C00524	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 2' HEIGHT, CONTAINER	EACH	157	157				
* C2C11024	SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 2' HEIGHT, CONTAINER	EACH	130	130				
X0300626	CURB AND GUTTER REMOVAL	FOOT	250	250				
X0301835	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1				
X0301892	MANHOLES, TYPE A, 8' -DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1				
* X0322323	WEED CONTROL, TEASEL	GALLON	0.5	0.5				
* X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	8	8				
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	23	23				
X0323794	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	4756	4756				
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	4756	4756				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A	BRIDGE SN 099-4648 STATE 100% X071-2A	RETAINING WALL SN 099-W012 STATE 100% Y007	TRAFFIC SIGNALS Y031-1F	OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	169		169			
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	2461			2461		
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	737			737		
X0329891	SILT CURTAIN	SQ YD	50	50				
X0712400	TEMPORARY PAVEMENT	SQ YD	5400	5400				
X3550705	BITUMINOUS BASE COURSE SUPERPAVE 10 1/4"	SQ YD	5880	5880				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	18	18				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2				
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	63	63				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	577	577				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	317	317				
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	48	48				
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	1025	1025				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	96	96				
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1			
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1			
X6022110	MANHOLES, TYPE A, 10' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
X6330075	RELOCATE TRAFFIC BARRIER TERMINAL, (TEMPORARY)	EACH	2	2				
X7030130	PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL	FOOT	26035	26035				
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1				1	
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	648				648	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. 8-2-05

5/20/2005 11:42:12 AM