

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-B-R-1&15N-3	WILL	143	4
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		
93.3/STATE 6.71/VILLAGE			62098	

93.3/STATE
6.71/VILLAGE

93.3/STATE
6.71/VILLAGE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A	BRIDGE SN 099-4648 STATE 100% X071-2A	RETAINING WALL SN 099-W012 STATE 100% Y007	TRAFFIC SIGNALS Y031-1F	OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D
50300300	PROTECTIVE COAT	SQ YD	1596	1	1464	132		
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	30		30			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	6385		5985	400		
* 50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1008			1008		
50800105	REINFORCEMENT BARS	POUND	50275		14790	35485		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	111,271		106,722	4,549		
50900105	ALUMINUM RAILING, TYPE L	FOOT	677		294	383		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	345		345			
51202700	DRIVING STEEL PILES	FOOT	345		345			
51203600	TEST PILE STEEL HP12X53	EACH	2		2			
51204600	METAL SHOES	EACH	20		20			
51500100	NAME PLATES	EACH	1		1			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	10	10				
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	1	1				
54213711	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 66"	EACH	1	1				
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	2	2				
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	182	182				
542D05479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	137	137				
550A0220	STORM SEWERS, CLASS A, TYPE 1 66"	FOOT	496	496				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	653	653				
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	656	656				
550A0500	STORM SEWERS, CLASS A, TYPE 2 60"	FOOT	1849	1849				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	410			410		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	408			408		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A	BRIDGE SN 099-4648 STATE 100% X071-2A	RETAINING WALL SN 099-W012 STATE 100% Y007	TRAFFIC SIGNALS Y031-1F	OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2				
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	5	5				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7				
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2				
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2				
60257700	MANHOLE ADJUSTING RING	EACH	2	2				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375	375				
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4				
63200310	GUARDRAIL REMOVAL	FOOT	420	420				
66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1	1				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	70	70				
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	120	120				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1464	1464				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26035	26035				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	181	181				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8273	8273				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES