

93.3/STATE
6.7%
VILLAGE

93.3/STATE
6.7%
VILLAGE

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|--|--------|------------------------|--|---------------------------------------|--|-------------------------|--|
| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A | BRIDGE SN 099-4648 STATE 100% X071-2A | RETAINING WALL SN 099-W012 STATE 100% Y007 | TRAFFIC SIGNALS Y031-1F | OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D |
| 89000100 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | | | 1 | |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 | | | | 1 | |
| * A2001720 | TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED | EACH | 12 | 12 | | | | |
| * A2002374 | TREE, BETULA NIGRA (RIVER BIRCH), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED | EACH | 6 | 6 | | | | |
| * A2005116 | TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER, BALLED AND BURLAPPED | EACH | 24 | 24 | | | | |
| * A2005614 | TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 22 | 22 | | | | |
| * A2006716 | TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED | EACH | 36 | 36 | | | | |
| * C2000524 | SHRUB, ARONIA MELANOCARPA (BLACK CHOKEBERRY), 2' HEIGHT, BALLED AND BURLAPPED | EACH | 10 | 10 | | | | |
| * C2012748 | SHRUB, VIBURNUM PRUNIFOLIUM (BLACKHAW VIBURNUM), 4' HEIGHT, BALLED AND BURLAPPED | EACH | 167 | 167 | | | | |
| * C2000524 | SHRUB, ARONIA MELANOCARPA (BLACK CHOKEBERRY), 2' HEIGHT, CONTAINER | EACH | 157 | 157 | | | | |
| * C2C11024 | SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 2' HEIGHT, CONTAINER | EACH | 130 | 130 | | | | |
| X0300626 | CURB AND GUTTER REMOVAL | FOOT | 250 | 250 | | | | |
| X0301835 | MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | EACH | 1 | 1 | | | | |
| X0301892 | MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | EACH | 1 | 1 | | | | |
| * X0322323 | WEED CONTROL, TEASEL | GALLON | 0.5 | 0.5 | | | | |
| * X0322859 | WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE | POUND | 8 | 8 | | | | |
| X0323426 | SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING | EACH | 23 | 23 | | | | |
| X0323794 | SEDIMENT CONTROL, SILT FENCE MAINTENANCE | FOOT | 4756 | 4756 | | | | |
| X0323973 | SEDIMENT CONTROL, SILT FENCE | FOOT | 4756 | 4756 | | | | |

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|---|-------|------------------------|--|---------------------------------------|--|-------------------------|--|
| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | URBAN WILL CO. US 30 @ LILY CACHE STATE 100% J000-2A | BRIDGE SN 099-4648 STATE 100% X071-2A | RETAINING WALL SN 099-W012 STATE 100% Y007 | TRAFFIC SIGNALS Y031-1F | OPTICON VILLAGE OF PLAINFIELD 100% Y031-3D |
| X0323988 | TEMPORARY SOIL RETENTION SYSTEM | SQ FT | 169 | | 169 | | | |
| * X0324455 | DRILLING AND SETTING SOLDIER PILES (IN SOIL) | CU FT | 2461 | | | 2461 | | |
| * X0324456 | DRILLING AND SETTING SOLDIER PILES (IN ROCK) | CU FT | 737 | | | 737 | | |
| X0329891 | SILT CURTAIN | SQ YD | 50 | 50 | | | | |
| X0712400 | TEMPORARY PAVEMENT | SQ YD | 5400 | 5400 | | | | |
| X3550705 | BITUMINOUS BASE COURSE SUPERPAVE 10 1/4" | SQ YD | 5880 | 5880 | | | | |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 10 | 10 | | | | |
| X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 18 | 18 | | | | |
| X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 2 | 2 | | | | |
| X4066414 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 | TON | 63 | 63 | | | | |
| X4066424 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50 | TON | 577 | 577 | | | | |
| X4066426 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 | TON | 317 | 317 | | | | |
| X4066614 | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 | TON | 48 | 48 | | | | |
| X4066616 | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70 | TON | 1025 | 1025 | | | | |
| X4067100 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50 | TON | 96 | 96 | | | | |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1 | EACH | 1 | | 1 | | | |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2 | EACH | 1 | | 1 | | | |
| X6022110 | MANHOLES, TYPE A, 10'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | | | | |
| X6330075 | RELOCATE TRAFFIC BARRIER TERMINAL, (TEMPORARY) | EACH | 2 | 2 | | | | |
| X7030130 | PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL | FOOT | 26035 | 26035 | | | | |
| * X8050015 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 1 | | | | 1 | |
| * X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 648 | | | | 648 | |

* SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES