

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90 *		COOK	598	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							S.N. 016-0142
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X92B-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	S.N. 016-1148
20200100	EARTH EXCAVATION	CU YD	215,989	215,989								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	965		965							
20800150	TRENCH BACKFILL	CY YD	33,825	33,825								
20900410	SAND BACKFILL	CU YD	680	680								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	215,074	215,074								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,865	1,865								
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	3,762	3,762								
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	3,762	3,762								
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	1,518	1,518								
25000210	SEEDING, CLASS 2A	ACRE	1	1								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	105	105								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	105	105								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	105	105								
25100115	MULCH, METHOD 2	ACRE	1	1								
25100630	EROSION CONTROL BLANKET	SQ YD	5,629	5,629								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	117	117								
28000400	PERIMETER EROSION BARRIER	FOOT	975	975								
28000510	INLET FILTERS	EACH	221	221								
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	224,179	224,179								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	452			452						
42001300	PROTECTIVE COAT	SQ YD	233,564	233,564								
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	146,651	146,651								
42101448	LUG SYSTEM COMPLETE 48'	EACH	3	3								
44000013	BITUMINOUS SURFACE REMOVAL, 5"	SQ YD	143			143						
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82			82						
44000100	PAVEMENT REMOVAL	SQ YD	161,041	161,041								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,313	6,313								
44000700	APPROACH SLAB REMOVAL	SQ YD	219			219						
44001980	CONCRETE BARRIER REMOVAL	FOOT	24,208	24,208								
44004250	PAVED SHOULDER REMOVAL	SQ YD	61,779	61,779								
44201423	CLASS C PATCHES, TYPE I, 16 INCH	SQ YD	25	25								
44201427	CLASS C PATCHES, TYPE II, 16 INCH	SQ YD	60	60								
44201431	CLASS C PATCHES, TYPE III, 16 INCH	SQ YD	50	50								
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	36	36								

62302 * (1818, ETC, 2324.6-1PIR-9

* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION
SUMMARY OF QUANTITIES
SCHEDULE

SCALE: NTS
DATE: 07/07/05

DRAWN BY: RA
CHECKED BY: JDC

S00-01
5:36:14 PM
6/29/2005