

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	90% FEDERAL / 10% STATE									
			URBAN TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	
50200100	STRUCTURE EXCAVATION	CU YD	3,909	1,214	2,695							
50300225	CONCRETE STRUCTURES	CU YD	916	51	865							
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,162.2	964	86	112.2						
50300260	BRIDGE DECK GROOVING	SQ YD	212			212						
50300300	PROTECTIVE COAT	SQ YD	4,710.0	2,815	1,570	257						68
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	655									655
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	40									40
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	16,237	16,237								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	196,985	65,625	109,910	21,450						
55100300	STORM SEWER REMOVAL 8"	FOOT	692	692								
55100400	STORM SEWER REMOVAL 10"	FOOT	6,619	6,619								
55100500	STORM SEWER REMOVAL 12"	FOOT	4,957	4,957								
55100700	STORM SEWER REMOVAL 15"	FOOT	3,199	3,199								
55100900	STORM SEWER REMOVAL 18"	FOOT	4,072	4,072								
55101100	STORM SEWER REMOVAL 21"	FOOT	613	613								
55101200	STORM SEWER REMOVAL 24"	FOOT	3,683	3,683								
55101300	STORM SEWER REMOVAL 27"	FOOT	685	685								
55101400	STORM SEWER REMOVAL 30"	FOOT	1,199	1,199								
55101600	STORM SEWER REMOVAL 36"	FOOT	328	328								
55101800	STORM SEWER REMOVAL 42"	FOOT	57	57								
59000100	EPOXY CRACK SEALING	FOOT	124									124
60107700	PIPE UNDERDRAINS 6"	FOOT	51,849	51,849								
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	636	636								
60109000	PIPE UNDERDRAINS, PERFORATED CORRUGATED STEEL PIPE 12"	FOOT	399	399								
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	1,100		1,100							
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	19	19								
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2								
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	266	266								
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2								
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	2	2								
60208210	CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	6	6								
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	47	47								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	151	151								
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6								

* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION
SUMMARY OF QUANTITIES
SCHEDULE

SCALE: NTS
DATE: 07/07/05
DRAWN BY: RA
CHECKED BY: JDC

S00-02

6/29/2005 5:36:39 PM \\s600\corporate\ADMIN\SHEET\S00-02.DWG