

EXISTING STORM SEWER SCHEDULE

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1575+91.3	53.9'	LT	1575+95.7	63.5'	LT	6.6										
1575+91.3	53.9'	LT	1577+41.4	53.2'	LT						146.2					140.7
1577+31.8	57.3'	LT	1577+39.2	7.8'	RT	61.5										0.0
1577+31.8	57.3'	LT	1577+41.4	53.2'	LT		6.4									0.6
1577+31.4	66.6'	LT	1577+41.4	53.2'	LT				12.8							4.9
1577+41.4	53.2'	LT	1579+49.8	54.7'	LT						204.4					213.9
1579+41.6	57.7'	LT	1579+32.4	8.3'	RT		62.7									22.5
1579+41.6	57.7'	LT	1579+49.8	54.7'	LT			4.7								
1579+43.3	66.2'	LT	1579+49.8	54.7'	LT			9.3								2.8
1579+49.8	54.7'	LT	1579+77.9	52.0'	LT						24.2					13.4
1579+77.9	52.0'	LT	1581+08.4	53.1'	LT						126.5					
1581+08.4	53.1'	LT	1581+19.7	57.6'	LT		8.2									0.7
1581+08.4	53.1'	LT	1581+17.2	66.5'	LT		12.1									1.2
1581+12.4	8.0'	RT	1581+19.7	57.6'	LT		62.0									
1581+08.4	53.1'	LT	1581+76.9	53.4'	LT				64.6							
1581+76.9	53.4'	LT	1581+82.5	66.6'	LT				10.4							3.4
1581+76.9	53.4'	LT	1581+84.4	57.4'	LT		4.5									1.2
1581+84.4	57.4'	LT	1581+93.3	8.3'	RT		62.3									22.1
1581+89.0	13.3'	RT	1581+93.3	8.3'	RT		2.6									0.1
1582+98.6	52.2'	LT	1582+98.1	5.2'	RT		53.3									11.6
1582+98.6	52.2'	LT	1583+08.3	66.8'	LT	13.6										0.8
1582+98.6	52.2'	LT	1583+07.2	57.2'	LT		6.0									0.4
1582+98.1	5.2'	RT	1583+12.6	8.0'	RT		10.8									0.5
1583+83.2	66.6'	LT	1583+93.79	51.8'	LT	14.2										1.4
1583+95.0	57.0'	LT	1583+93.79	51.8'	LT		1.4									
1583+93.79	51.8'	LT	1583+92.8	4.1'	RT		51.9									17.5
1583+75.7	11.5'	RT	1583+83.4	1.9'	RT	8.4										1.0
1583+83.4	1.9'	RT	1583+92.8	4.1'	RT	5.7										0.3
1583+92.8	4.1'	RT	1585+93.4	4.3'	RT						196.6					145.4
1585+77.1	7.9'	RT	1585+93.4	4.3'	RT		12.8									9.6
1585+93.4	4.3'	RT	1585+93.4	52.2'	LT		52.5									
1585+83.6	57.3'	LT	1585+93.4	52.2'	LT		7.0									0.7
1585+82.9	66.6'	LT	1585+93.4	52.2'	LT	13.8										1.2
1585+93.4	4.3'	RT	1587+93.3	4.2'	RT					195.9						270.0
1587+78.2	8.0'	RT	1587+93.3	4.2'	RT		11.6									
1587+93.3	4.2'	RT	1587+93.5	52.4'	LT		52.6									
1587+83.9	57.4'	LT	1587+93.5	52.4'	LT		6.8									0.4
1587+83.6	66.7'	LT	1587+93.5	52.4'	LT	13.4										1.0
1587+93.3	4.2'	RT	1589+88.9	4.0'	RT			191.6								246.9
1589+77.5	8.0'	RT	1589+88.9	4.0'	RT		8.2									
1589+88.9	4.0'	RT	1589+91.9	52.9'	LT				52.9							20.7
1589+83.4	57.8'	LT	1589+91.9	52.9'	LT		5.9									0.4
1589+82.9	66.8'	LT	1589+91.9	52.9'	LT	12.6										1.2
1591+90.1	4.1'	RT	1593+09.0	4.2'	RT					114.9						146.0
1591+41.1	7.9'	RT	1591+57.4	4.4'	RT		12.7									0.7

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1591+57.4	4.4'	RT	1591+90.1	4.1'	RT				123.4	28.8						
1591+57.4	4.4'	RT	1591+58.2	51.6'	LT			52.0								
1591+48.4	66.7'	LT	1591+58.2	51.6'	LT	14.0										
1591+49.2	57.5'	LT	1591+58.2	51.6'	LT			6.8								
1592+99.7	7.9'	RT	1593+09.0	4.2'	RT		6.1									1.5
1593+09.0	4.2'	RT	1593+07.7	57.4'	LT		57.6									5.2
1593+09.0	4.2'	RT	1594+19.0	4.1'	RT				105.9							107.5
1594+08.6	8.3'	RT	1594+19.0	4.1'	RT			7.2								6.9
1594+19.0	4.1'	RT	1594+18.4	51.9'	LT			52.0								
1594+07.4	57.3'	LT	1594+18.4	51.9'	LT			8.3								0.7
1594+08.2	66.9'	LT	1594+18.4	51.9'	LT	14.2										0.8
1597+48.4	4.1'	RT	1597+52.6	7.7'	RT			1.5								
1597+48.4	4.1'	RT	1597+48.9	51.8'	LT			51.9								
1597+48.9	51.8'	LT	1597+59.7	57.7'	LT	8.3										0.4
1597+48.9	51.8'	LT	1597+58.1	66.9'	LT	13.7										1.1
1597+48.4	4.1'	RT	1598+48.4	4.6'	RT				96.0							52.7
1598+48.4	4.6'	RT	1598+54.9	7.8'	RT		3.3									
1598+48.4	4.6'	RT	1598+48.5	51.9'	LT	52.5										
1598+48.5	51.9'	LT	1598+58.1	67.0'	LT	13.8										0.7
1598+48.5	51.9'	LT	1598+59.0	57.8'	LT	8.0										
1598+48.4	4.6'	RT	1599+98.9	4.3'	RT				146.5							155.8
1599+98.9	4.3'	RT	1600+07.6	7.4'	RT			5.3								3.5
1599+98.9	4.3'	RT	1599+98.5	52.1'	LT			52.4								
1599+98.5	52.1'	LT	1600+06.9	57.8'	LT	6.2										0.3
1599+98.5	52.1'	LT	1600+08.1	67.1'	LT	13.8										0.9
1599+98.9	4.3'	RT	1600+68.6	5.6'	RT				65.7							77.8
1600+68.6	5.6'	RT	1601+77.6	4.0'	RT				105.1							135.0
1601+77.6	4.0'	RT	1601+83.7	7.6'	RT			3.1								
1601+77.6	4.0'	RT	1601+78.5	52.2'	LT											
1601+78.5	52.2'	LT	1601+96.5	57.6'	LT	14.8										1.2
1601+78.5	52.2'	LT	1601+98.6	67.0'	LT	21.0										2.2
1603+79.0	52.7'	LT	1603+88.6	67.0'	LT	13.2										1.0
1603+79.0	52.7'	LT	1603+88.4	57.9'	LT	6.7										0.3
1603+78.6	3.9'	RT	1603+79.0	52.7'	LT				52.6							
1603+78.6	3.9'	RT	1603+84.6	7.6'	RT			3.0								
1603+78.6	3.9'	RT	1605+78.6	4.0'	RT				196.0							182.1
1605+78.6	4.0'	RT	1605+84.8	7.6'	RT	3.2										
1605+78.6	4.0'	RT	1605+79.0	52.3'	LT			52.2								
1605+79.0	52.3'	LT	1605+89.3	57.8'	LT	7.7										
1605+79.0	52.3'	LT	1605+88.6	66.8'	LT	13.4										1.2
1605+94.5	8.0'	RT	1607+09.9	4.3'	RT					127.3						120.0
1607+09.9	4.3'	RT	1607+14.3	7.6'	RT			1.5								
1607+09.9	4.3'	RT	1607+08.6	51.9'	LT			52.1								14.5
1607+08.6	51.9'	LT	1607+19.0	66.8'	LT	14.3										0.7
1607+08.6	51.9'	LT	1607+20.6	57.9'	LT			9.4								

BOWMAN, BARRETT & ASSOCIATES INC  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
31ST STREET TO 71ST STREET  
SB EXPRESS LANE RECONSTRUCTION  
DRAINAGE SCHEDULES  
EXISTING STORM SEWER REMOVAL  
SCALE: 1"=N.T.S. DRAWN BY: OC  
DATE: 07/07/05 CHECKED BY: DDM