

### SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
*C2012772	SHRUB, VIBURNUM PRUNIFOLIUM, (BLACKHAW VIBURNUM), 6' HEIGHT. BALLED AND BURLAPPED	EACH	12	12			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
<del>X0323000</del>	<del>0 CIRCUIT E10/120 PANEL</del>	<del>EACH</del>	<del>1</del>				
<del>X0323001</del>	<del>METER SOCKET PER 00M ED</del>	<del>EACH</del>	<del>1</del>				
<del>X0323002</del>	<del>TEMPORARY ELECTRICAL SERVICE CONNECTION</del>	<del>EACH</del>	<del>1</del>				
<del>X0323153</del>	<del>ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6-16 (GREEN)</del>	<del>FOOT</del>	<del>300</del>				<del>300</del>
X0712400	TEMPORARY PAVEMENT	SQ YD	4855	4855			
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	315	315			
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	369	369			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3			
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	78	78			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	250	250			
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	250	250			
<del>X0110112</del>	<del>REMOVE TEMPORARY LIGHTING UNITS</del>	<del>L SUM</del>	<del>1</del>				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z002800	FENCE REMOVAL	FOOT	214	214			
<del>Z0024100</del>	<del>FILTER FABRIC</del>	<del>SQ YD</del>	<del>101</del>	<del>107</del>			
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	8	8			
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	8	8			

△ SFTY-3U

### SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
XX004900	TURF REINFORCEMENT MAT	SQ YD	75	75			
XX001452	CONCRETE MASONRY BULKHEAD	EACH	1			1	
*X8210405	LUMINAIRE SHIELD	EACH	1				1
Z0076600	TRAINEES	HR	1,000	1,000			
B0400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1
B0400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1				1
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6				6
X0324949	100 A FUSED DISCONNECT SWITCH NEMA 4X ENCLOSURE	EACH	1				1

© 4080

\* SPECIALTY ITEM

△ Rev. 4-14-05



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
U.S. ROUTE 14 OVER LAWRENCE CREEK  
SUMMARY OF QUANTITIES

DATE: 2-15-05

DRAWN BY CLG  
CHECKED BY JJD

#62391

3287SHT3.DGN