



COMPLETE COMMODITY CODE NO. 05-6610-5310M

CODE NO.	MATERIALS	SIZE	QUAN.
(1) 05-6610-5310	PRE-CAST HANDHOLE	30"X36"	1
(2) 05-9075-5470	STONE 3/4" CRUSHED	BAG	5
(2) 05-5082-5330	SOND TUBE	30"	1
(2) 05-5082-5342	SOND TUBE	42"	1
(2) 05-3267-2940	CONC. REDI-MIX	CU. YD.	1/2
(2) 57-0770-0000	6" X 6" MESH	36"X10'	1
05-1452-9720	BRICK		24
02-4299-5524	FRAME MANHOLE	24"	1
02-4574-5040	COVER, MANHOLE	24"	1
09-7796-9312	GROUND ROD	3/4"X12'	1
09-2630-3240	GROUND CLAMP		1

- (1) PRE-CAST HANDHOLE SHALL INCLUDE CABLE HOOKS AND CONDUIT KNOCKOUTS.  
 (2) THESE ITEMS ARE FOR POURED-IN-PLACE HANDHOLES ONLY.

**CONSTRUCTION NOTES:**

- 8" BED OF STONE FOR DRAINAGE.
- ALL METALLIC CONDUITS ENTERING HANDHOLE SHALL EXTEND MINIMUM 1" & MAXIMUM 3" INSIDE INNER WALL AND BE EQUIPPED WITH AN APPROVED TYPE OF THREADED GROUNDING BUSHING.

B	12-23-00	ADDED CABLE HOOKS PER COMMISSIONER MURPHY	BOE/RED
A	12-8-95	REDRAW (CAD)	MP
	DATE	REVISION	
30" DIA. CONCRETE HANDHOLE			
CITY OF CHICAGO DEPT. OF CONCRETE AND ASPHALT DIVISION OF ELECTRICITY DIVISION OF STRUCTURAL ENGINEERING			
DEPARTMENT	ENGINEER	DESIGNER	TRACER
M. PATTON	B. CARTER	DEBARTOLO	
SUPERVISING ENGINEER	ETEC. DESIGN ENGINEER		
ENGINEER OF ELECTRICITY			UWG. NO.
DEPT. CHIEF OF ELECTRICITY			867
DEPT. COMMISSIONER			
SIZE: 11"	SCALE: NONE	DATE: 12-8-95	

BOE-5

REVISIONS	
NAME	DATE

02/02/2005 09:09:55 AM