

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	3130(A&B)RS-1	COOK	29	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62921

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18				
40600300	AGGREGATE (PRIME COAT)	TON	87	87				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	333	333				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	167	167				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	12157	12157				
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	31420	31420				
44000116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD	744	744				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	152	152				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1201	1201				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	314	314				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	491	491				
55039700	STORM SEWER TO BE CLEANED	FOOT	100	100				
60250200	CATCH BASIN TO BE ADJUSTED	EACH	2	2				
60260100	INLETS TO BE ADJUSTED	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	30	30				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	17	17				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6816	6816				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	105	105				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE 1000-2A				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16580	16580				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1180	1180				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	652	652				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	648	648				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	852	852				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	105	105				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16580	16580				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1180	1180				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	652	652				
* 78000610	THERMOPLASTIC PAVEMENT MARKING - LINE 16"	FOOT	87	87				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	648	648				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	516	516				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	516	516				
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	2	2				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1076	1076				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103				
X4066548	POLYMERIZED BITUMINOUS CONC. SURFACE COURSE, SUPER PAVE, MIX. "F", N90	TON	4350	4350				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD) SUPERPAVE, IL-4.75, N50	TON	2730	2730				
Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	30	30				
Z0018500	DRAINAGE STRUCTURE TO BE CLEANED	EACH	57	57				
Z0048665	RAILROAD PROTECTION LIABILITY INSURANCE	L SUM	1	1				

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
**IL RTE. 43 (HARLEM AVE.)**