

F.A.P. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	2005-015 RS	COOK	18	3
FED. ROAD DIST. NO. 1		ILLINOIS		HIGHWAY PROJECT
CONTRACT 62938				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3					
40600300	AGGREGATE (PRIME COAT)	TON	14	14					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	115	115					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	270	270					
42001300	PROTECTIVE COAT	SQ YD	25	25					
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	7000	7000					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	300	300					
44000120	BITUMINOUS REMOVAL OVER PATCHES 5"	SQ YD	950	950					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150					
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	150	150					
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	150	150					
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	400	400					
55039700	STORM SEWERS TO BE CLEANED	FOOT	600	600					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	14	14					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7					
60404940	FRAMES AND GRATES, TYPE 23	EACH	1	1					
60405740	FRAMES AND GRATES TO BE REMOVED	EACH	1	1					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1400	1400					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4300	4300					

* SPECIALITY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN I000-2A					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	400	400					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	90	90					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2300	2300					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4300	4300					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	400	400					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	90	90					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	80	80					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	690	690					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	295	295					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

6/4/2005 8:17:06 AM