| F.A. RTE. 1 | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 375 | 3035-Z-Y-1-RS-1 | COOK | 23 | 23 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

**62941**

1700 (68")

175 (7") — 1350 (54") — 175 (7")

① 

1125 (45")

175 175 125 175 175 (7")(7")(5")(7")(7")

175 175 125 175 (7")(7")(5")(7")

ROAD WORK

AHEAD

EXPECT DELAYS

1" BLACK BORDER

2.1 m MIN. (7')

USE APPROPRIATE
MONTH AND DATE
FOR CONTRACT

②

275 (11")  BEGINS   XXX   XX

1450 (58")

## NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE SHOWN.

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|---|---|---|
| NAME | DATE | |
| R. MIRS | 9-15-97 | |
| R. MIRS | 12-11-97 | TEMPORARY INFORMATION SIGNING |
| T. RAMMACHER | 2-2-99 | |
| | | |
| | | |
| | | SCALE: |
| | | DATE 6/4/2005 |

DRAWN BY: BUR. OF DESIGN
CHECKED BY

TC22
REVISION DATE: 02/02/99