

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
FAP 326	107 CRC-PP-3	KANE	13	8

**PAVEMENT PATCHING SCHEDULE**

Northbound ILLINOIS ROUTE 47  
BLISS RD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2			
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE	
70	84+74	13 x 12	17.3	III				
71	85+46	8 x 6	5.3	II				
72	85+66	14 x 6	9.3	II				
73	86+45	20 x 12	26.7	IV				
74	91+00	7 x 6	4.7	I				
75	91+75				16 x 12	21.3	III	
76	92+16				8 x 6	5.3	II	
77	93+13	10 x 6	6.7	II				
78	98+83	20 x 12	26.7	IV				
79	101+97	15 x 12	20.0	III				
80	104+72				6 x 12	8.0	II	
	110+84	ENDING STATION OF CRC PAVEMENT						
81	154+39	8 x 12	10.7	II				
82	156+49	9 x 6	6.0	II				
83	156+63	14 x 12	18.7	III				
84	156+89	6 x 12	8.0	II				
85	158+49	10 x 6	6.7	II				
86	159+27	6 x 12	8.0	II				
87	160+16	13 x 12	17.3	III				
88	160+45	20 x 6	13.3	II				
89	160+71	13 x 12	17.3	III				
90	161+20	7 x 12	9.3	II				
91	161+33	14 x 12	18.7	III				
92	161+53	21 x 6	14.0	II				
93	161+74	10 x 12	13.3	II				
94	161+96	14 x 6	9.3	II				
95	162+16	12 x 6	8.0	II				
96	162+35	11 x 6	7.3	II				
97	162+52	12 x 6	8.0	II	12 x 12	16.0	III	
98	162+92				5 x 12	6.7	II	
99	163+18				5 x 12	6.7	II	
100	163+28				27 x 12	36.0	IV	
101	164+11				6 x 12	8.0	II	
102	164+23				11 x 12	14.7	II	
103	164+40				14 x 12	18.7	III	
104	164+60				51 x 12	68.0	IV	
105	165+17				17 x 12	22.7	III	

**PAVEMENT PATCHING SCHEDULE**

Northbound ILLINOIS ROUTE 47  
BLISS RD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

**CONTRACT 62943**

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2			
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE	
106	165+66				6 x 12	8.0	II	
107	165+85				11 x 12	14.7	II	
108	166+15				12 x 6	8.0	II	
109	166+38				15 x 12	20.0	III	
110	166+64	15 x 6	10.0	II	15 x 12	20.0	III	
111	166+85	9 x 6	6.0	II	9 x 12	12.0	II	
112	167+00	11 x 6	7.3	II	11 x 12	14.7	II	
113	167+15	17 x 6	11.3	II	17 x 12	22.7	III	
114	167+49	8 x 12	10.7	II	8 x 12	10.7	II	
115	168+19	15 x 6	10.0	II	15 x 6	10.0	II	
116	168+85				8 x 12	10.7	II	
	170+22	SOUTH BRIDGE JOINT						
	171+88	NORTH BRIDGE JOINT						
117	173+27				6 x 12	8.0	II	
118	174+13				15 x 12	20.0	III	
119	174+35				17 x 12	22.7	III	
120	174+58				11 x 12	14.7	II	
121	174+76				5 x 12	6.7	II	
122	175+39	12 x 6	8.0	II				
123	175+45				8 x 12	10.7	II	
124	175+59				5 x 12	6.7	II	
125	175+83				6 x 12	8.0	II	
126	175+95	16 x 6	10.7	II	20 x 6	13.3	II	
127	176+22	14 x 6	9.3	II	14 x 6	9.3	II	
128	176+42	11 x 6	7.3	II	11 x 12	14.7	II	
129	176+60				17 x 12	22.7	III	
130	176+82	18 x 6	12.0	II	18 x 12	24.0	III	
131	177+06	67 x 6	44.7	IV	61 x 12	81.3	IV	
132	177+79				10 x 12	13.3	II	
133	177+94	14 x 6	9.3	II				
134	178+15	15 x 12	20.0	III				
135	178+18				12 x 12	16.0	III	
136	178+35	14 x 6	9.3	II	14 x 12	18.7	III	
137	178+56	6 x 12	8.0	II	6 x 12	8.0	II	
138	178+69	12 x 12	16.0	III	12 x 12	16.0	III	
139	178+88	30 x 6	20.0	III				
140	178+89				30 x 12	40.0	IV	

ILLINOIS DEPARTMENT OF TRANSPORTATION

**PAVEMENT PATCHING SCHEDULE**