

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
FAP 326	107 CRC-PP-3	KANE	13	9

**PAVEMENT PATCHING SCHEDULE**  
Northbound ILLINOIS ROUTE 47  
BLISS RD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
141	179+24				16 x 6	10.7	II
142	179+46	10 x 6	6.7	II	10 x 6	6.7	II
143	179+62	20 x 6	13.3	II	20 x 6	13.3	II
144	179+88	13 x 6	8.7	II	13 x 6	8.7	II
145	180+01	5 x 12	6.7	II	5 x 12	6.7	II
146	180+13	11 x 6	7.3	II	11 x 12	14.7	II
147	180+29				6 x 12	8.0	II
148	180+44	7 x 6	4.7	I	7 x 12	9.3	II
149	180+59	16 x 6	10.7	II	16 x 12	21.3	III
150	180+81	13 x 6	8.7	II	13 x 12	17.3	III
151	181+00	16 x 6	10.7	II	16 x 6	10.7	II
152	181+46	14 x 6	9.3	II			
153	181+66	16 x 6	10.7	II			
154	181+88	16 x 12	21.3	III			
155	182+15	10 x 12	13.3	II			
156	182+53	5 x 12	6.7	II			
157	184+12	30 x 6	20.0	III			
158	184+57	8 x 6	5.3	II			
159	184+74	5 x 12	6.7	II			
160	184+86	30 x 6	20.0	III			
161	185+45	16 x 6	10.7	II			
162	185+67	36 x 6	24.0	III			
163	186+23	12 x 12	16.0	III			
164	186+57	24 x 6	16.0	III			
165	186+87	36 x 12	48.0	IV			
166	187+36	11 x 12	14.7	II			
167	187+60	7 x 12	9.3	II			
168	187+97	13 x 12	17.3	III			
	188+20	ENDING STATION OF CRC PAVEMENT					
	188+96	CENTERLINE-SEAVEY RD.					

**PAVEMENT PATCHING SCHEDULE**  
Southbound ILLINOIS ROUTE 47  
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD. **CONTRACT 62943**

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
	0+00	CENTERLINE-SEAVEY RD.					
169	0+76	30 x 6	20.0	III			
170	1+05	6 x 12	8.0	II			
171	1+17	6 x 12	8.0	II			
172	1+29	13 x 12	17.3	III			
173	1+49	12 x 6	8.0	II			
174	1+66	13 x 6	8.7	II			
175	1+87	6 x 12	8.0	II			
176	1+99	10 x 12	13.3	II			
177	2+14	10 x 12	13.3	II			
178	2+30	8 x 12	10.7	II			
179	2+44	10 x 6	6.7	II			
180	2+60	15 x 12	20.0	III			
181	2+81	14 x 12	18.7	III			
182	3+64	5 x 12	6.7	II			
183	4+01	9 x 6	6.0	II			
184	4+16	32 x 12	42.7	IV			
185	7+28				5 x 12	6.7	II
186	8+35	18 x 6	12.0	II			
187	8+72	6 x 12	8.0	II	6 x 12	8.0	II
188	9+60				15 x 12	20.0	III
189	10+14	17 x 12	22.7	III	17 x 12	22.7	III
190	10+39	9 x 6	6.0	II	9 x 12	12.0	II
191	10+56	7 x 6	4.7	I	7 x 12	9.3	II
192	10+73				23 x 6	15.3	III
193	11+02				86 x 12	114.7	IV
194	12+24				13 x 12	17.3	III
195	12+44	6 x 12	8.0	II	6 x 12	8.0	II
196	13+19				8 x 12	10.7	II
197	13+45				16 x 6	10.7	II
198	13+95				6 x 12	8.0	II
199	14+06				32 x 6	21.3	III
200	14+56				5 x 12	6.7	II
201	14+91				8 x 6	5.3	II
	16+86	NORTH BRIDGE JOINT					
	18+52	SOUTH BRIDGE JOINT					
202	19+81				14 x 12	18.7	III

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**PAVEMENT PATCHING SCHEDULE**