

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 326	107 CRC-PP-3	KANE	13	10

PAVEMENT PATCHING SCHEDULE
Southbound ILLINOIS ROUTE 47
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD.

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
203	20+10	14 x 6	9.3	II	14 x 6	9.3	II
204	24+43	132 x 6	88.0	IV			
	26+22	CENTERLINE-FINLEY RD.					
205	26+36	25 x 6	16.7	III			
206	26+59	11 x 6	7.3	II			
207	28+87	30 x 6	20.0	III			
208	29+71	6 x 12	8.0	II			
209	34+66	8 x 12	10.7	II			
	34+74	ENDING STATION OF CRC PAVEMENT					
	78+29	START OF CRC PAVEMENT					
210	80+13	13 x 12	17.3	III			
211	81+44				15 x 6	10.0	II
212	82+06				12 x 12	16.0	III
213	83+90				10 x 6	6.7	II
214	87+95	22 x 12	29.3	IV			
215	88+49	8 x 6	5.3	II			
216	89+50	12 x 12	16.0	III			
217	98+15				12 x 12	16.0	III
218	102+09				12 x 12	16.0	III
219	107+96	47 x 6	31.3	IV			
220	108+01				8 x 6	5.3	II
221	108+60	23 x 6	15.3	III	23 x 6	15.3	III
222	108+93				12 x 6	8.0	II
223	109+08				30 x 12	40.0	IV
224	111+04				50 x 12	66.7	IV
225	111+70	22 x 12	29.3	IV	17 x 12	22.7	III
226	112+19	20 x 6	13.3	II			
227	112+96				40 x 6	26.7	IV
	113+29	CENTERLINE-HARTER RD.					
228	115+64	25 x 6	16.7	III			
229	116+54				18 x 12	24.0	III
230	117+68				11 x 12	14.7	II
231	118+80				6 x 12	8.0	II
232	119+49				33 x 12	44.0	IV
233	119+86	19 x 6	12.7	II			
234	120+13				7 x 6	4.7	I
235	121+18				8 x 6	5.3	II

PAVEMENT PATCHING SCHEDULE
Southbound ILLINOIS ROUTE 47
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD.

CONTRACT 62943

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
236	122+13	31 x 6	20.7	III			
237	122+36	11 x 6	7.3	II			
238	124+92				9 x 6	6.0	II
239	125+69	20 x 6	13.3	II			
240	128+33				10 x 6	6.7	II
241	128+55				14 x 12	18.7	III
242	130+37				11 x 6	7.3	II
243	131+54	7 x 6	4.7	I			
	132+65	CENTERLINE-WAUBONSEE RD.					
244	132+67				16 x 12	21.3	III
245	134+38				12 x 6	8.0	II
246	137+25				13 x 12	17.3	III
247	137+81	15 x 6	10.0	II	15 x 6	10.0	II
248	138+94	34 x 6	22.7	III	34 x 6	22.7	III
249	139+40				10 x 6	6.7	II
250	140+12				17 x 6	11.3	II
251	142+67	15 x 12	20.0	III			
252	143+13	42 x 12	56.0	IV			
253	143+61				15 x 6	10.0	II
254	144+06	29 x 12	38.7	IV			
255	144+12				12 x 6	8.0	II
256	145+63				13 x 6	8.7	II
257	148+86				8 x 6	5.3	II
258	152+56	15 x 12	20.0	III			
259	154+06	10 x 12	13.3	II	10 x 12	13.3	II
260	154+69				10 x 12	13.3	II
261	156+17				7 x 6	4.7	I
	161+59	CENTERLINE-KEDEKA RD.					
262	164+91				16 x 12	21.3	III
263	171+05				11 x 12	14.7	II
264	171+21				35 x 6	23.3	III
265	172+41				10 x 6	6.7	II
266	176+86	19 x 12	25.3	IV			
267	177+52	14 x 12	18.7	III			
268	182+88				15 x 6	10.0	II
269	183+79				12 x 6	8.0	II
270	184+48				15 x 6	10.0	II

ILLINOIS DEPARTMENT OF TRANSPORTATION
PAVEMENT PATCHING SCHEDULE