

62945

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	541X-1	COOK	7	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

62945

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		LOCATION 1		LOCATION 2				
				SFTY-2A 100% STATE	SFTY-2A 100% VILLAGE	SFTY-2A 100% STATE				
42101300	PROTECTIVE COAT	SQ YD	535	490	45					
44000300	CURB REMOVAL	FOOT	1150	1150						
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3500	3500						
44003100	MEDIAN REMOVAL	SQ FT	340		340					
60600605	CONCRETE CURB, TYPE B	FOOT	1040	1040						
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3300	3300						
60624600	CORRUGATED MEDIAN	SQ FT	630	290	340					
67100100	MOBILIZATION	L SUM	1	0.6	0.4					
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	0.6	0.4					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5					
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	7.5	7.5						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1350	1350						
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	51.4	51.4					
X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	1391	1187	204					
60617100	DOWEL BARS 1"	EACH	330	330	330					
X0325055	CONCRETE MEDIAN SURFACE, (STAMPING)	SQ FT	3300		3300					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 6/13/2005