

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-41)	LASALLE	33	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS		FED. AID PROJECT	

SUMMARY OF QUANTITIES		90% FEDERAL	10% STATE
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:	
		UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1924
20800150	TRENCH BACKFILL	CU YD	84.5
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	18312
25000210	SEEDING, CLASS 2A	ACRE	1.46
25000400	NITOGEN FERTILIZER NUTRIENT	POUND	131
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	131
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	131
25100115	MULCH, METHOD 2	ACRE	1.46
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	874
28000500	INLET AND PIPE PROTECTION	EACH	2
31100900	SUB-BASE GRANULAR MATERIAL, TYPE A 10"	SQ YD	18312
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	15101
48101200	AGGREGATE SHOULDERS, TYPE B	TON	553.8
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	1600
50105220	PIPE CULVERT REMOVAL	FOOT	66
50800105	REINFORCEMENT BARS	POUND	26
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
54248510	CONCRETE COLLAR	CU YD	0.48
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	1077
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	33
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1
60247160	DRAINAGE STRUCTURE, TYPE 1 WITH TWO TYPE 20 FRAME & GRATES	EACH	1
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1487.5
X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	EACH	2
X6050700	REMOVE INLET BOX	EACH	3
X6331009	REMOVE AND REPLACE STEEL PLATE BEAM GUARDRAIL, SPECIAL	FOOT	200
Δ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0041500	PLUG EXISTING CULVERTS	EACH	1
Z0075310	TIE BARS 3/4"	EACH	4111
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	675

• SPECIALTY ITEMS
 Δ SFTY 3N

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITY SCALE: VERT. DRAWN BY HORIZ. CHECKED BY DATE