

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4)I	LASALLE	33	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SEEDING & EROSION CONTROL SCHEDULE

LOCATION	SEEDING CL 2A	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	INLET AND PIPE PROTECTION	MULCH METHOD 2
COUNTY	ACRE	POUNDS	POUNDS	POUNDS	POUNDS	EACH	ACRE
LaSalle							
SOUTH CROSSOVER							
STA. 776+00 TO STA 777+00	0.006	3	0.52	0.52	0.52		0.006
STA 777+00 TO STA 778+00	0.018	11	1.65	1.65	1.65		0.018
STA 778+00 TO STA 779+00	0.028	17	2.48	2.48	2.48		0.028
STA 779+00 TO STA 780+00	0.040	24	3.62	3.62	3.62		0.040
STA 780+00 TO STA 781+00	0.061	37	5.48	5.48	5.48		0.061
STA 781+00 TO STA 782+00	0.064	39	5.79	5.79	5.79		0.064
STA 782+00 TO STA 783+00	0.048	29	4.34	4.34	4.34	1	0.048
STA 783+00 TO STA 784+00	0.030	18	2.69	2.69	2.69		0.030
STA 784+00 TO STA 785+00	0.010	6	0.93	0.93	0.93		0.010
STA 785+00 TO STA 786+00	0	0	0.00	0.00	0.00		0.000
STA 786+00 TO STA 787+00	0	0	0.00	0.00	0.00		0.000
STA 787+00 TO STA 788+00	0	0	0.00	0.00	0.00		0.000
STA 788+00 TO STA 789+00	0	0	0.00	0.00	0.00		0.000
STA 790+00 TO STA 791+00	0	0	0.00	0.00	0.00		0.000
STA 791+00 TO STA 791+55	0.009	6	0.85	0.85	0.85		0.009
STA 791+55 TO STA 791+70	0.006	4	0.54	0.54	0.54		0.006
STA 791+70 TO STA 792+00	0.045	27	4.03	4.03	4.03		0.045
STA 792+00 TO STA 792+85	0.031	19	2.81	2.81	2.81	1	0.031
STA 792+85 TO STA 793+00	0.051	30	4.55	4.55	4.55		0.051
STA 793+00 TO STA 794+00	0.091	54	8.16	8.16	8.16		0.091
STA 794+00 TO STA 795+00	0.124	74	11.16	11.16	11.16		0.124
STA 795+00 TO STA 796+00	0.117	70	10.54	10.54	10.54		0.117
STA 796+00 TO STA 797+00	0.078	47	7.02	7.02	7.02		0.078
STA 797+00 TO STA 798+00	0.065	39	5.89	5.89	5.89		0.065
STA 798+00 TO STA 799+00	0.077	46	6.92	6.92	6.92		0.077
STA 799+00 TO STA 800+00	0.062	37	5.58	5.58	5.58		0.062
STA 800+00 TO STA 801+00	0.031	19	2.79	2.79	2.79		0.031
STA 801+00 TO STA 802+00	0.039	23	3.51	3.51	3.51		0.039
STA 802+00 TO STA 803+00	0.052	31	4.65	4.65	4.65		0.052
STA 803+00 TO STA 804+00	0.046	28	4.13	4.13	4.13		0.046
STA 804+00 TO STA 805+00	0.052	31	4.65	4.65	4.65		0.052
STA 805+00 TO STA 806+00	0.056	34	5.06	5.06	5.06		0.056
STA 806+00 TO STA 807+00	0.048	29	4.34	4.34	4.34		0.048
NORTH CROSSOVER							
STA 885+35 TO STA 887+00	0.021	12	1.86	1.86	1.86		0.021
STA 887+00 TO STA 888+50	0.009	6	0.85	0.85	0.85		0.009
	0.022	13	2.01	2.01	2.01		0.022
	0.018	11	1.65	1.65	1.65		0.018
LINE TOTAL	1.46	874	131.0	131.0	131.0	2	1.46

1. NOTE: QUANTITY FOR TEMPORARY SEEDING AVAILABLE FOR 6 APPLICATIONS

EARTHWORK SCHEDULE

LOCATION IROQUOIS COUNTY	EARTH EXCAVATION	EARTH EX. ADJUSTED FOR SHRINKAGE (0.75)	EMBANKMENT	FURNISHED EXCAVATION WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD
SOUTH CROSSOVER				
STA 776+00 TO STA 777+00	59.3	44.48	7.4	37.08
STA 777+00 TO STA 778+00	66.7	50.03	3.7	46.33
STA 778+00 TO STA 779+00	90.7	68.03	18.5	49.53
STA 779+00 TO STA 780+00	116.7	87.53	55.6	31.93
STA 780+00 TO STA 781+00	125.9	94.43	72.2	22.23
STA 781+00 TO STA 782+00	122.2	91.65	74.1	17.55
STA 782+00 TO STA 783+00	103.7	77.78	68.5	9.28
STA 783+00 TO STA 784+00	94.4	70.80	35.2	35.60
STA 784+00 TO STA 785+00	218.5	163.88	5.6	158.28
STA 785+00 TO STA 786+00	211.1	158.33	16.7	141.63
STA 786+00 TO STA 787+00	87	65.25	27.8	37.45
STA 787+00 TO STA 788+00	77.8	58.35	27.8	30.55
STA 788+00 TO STA 789+00	92.6	69.45	38.9	30.55
STA 789+00 TO STA 790+00	107.4	80.55	70.4	10.15
STA 790+00 TO STA 791+00	105.6	79.20	88.9	-9.70
STA 791+00 TO STA 791+55	64.2	48.15	44.8	3.35
STA 791+55 TO STA 791+70	21.1	15.83	50	-34.18
STA 791+70 TO STA 792+00	159.3	119.48	3.1	116.38
STA 792+00 TO STA 792+85	154.3	115.73	45.6	70.13
STA 792+85 TO STA 793+00	24.7	18.53	13.9	4.63
STA 793+00 TO STA 794+00	203.7	152.78	90.7	62.08
STA 794+00 TO STA 795+00	188.9	141.68	64.8	76.88
STA 795+00 TO STA 796+00	161.1	120.83	27.8	93.03
STA 796+00 TO STA 797+00	144.4	108.30	18.5	89.80
STA 797+00 TO STA 798+00	148.1	111.08	18.5	92.58
STA 798+00 TO STA 799+00	155.6	116.70	20.4	96.30
STA 799+00 TO STA 800+00	157.4	118.05	16.7	101.35
STA 800+00 TO STA 801+00	155.6	116.70	22.2	94.50
STA 801+00 TO STA 802+00	153.7	115.28	24.1	91.18
STA 802+00 TO STA 803+00	153.7	115.28	16.7	98.58
STA 803+00 TO STA 804+00	150	112.50	14.8	97.70
STA 804+00 TO STA 805+00	125.9	94.43	11.1	83.33
STA 805+00 TO STA 806+00	111.1	83.33	7.4	75.93
STA 806+00 TO STA 807+00	57.4	43.05	3.7	39.35
NORTH CROSSOVER				
STA 886+00 TO STA 887+00	63	47.25	3.7	43.55
STA 887+00 TO STA 888+00	83.3	62.48	3.7	58.78
STA 888+00 TO STA 889+00	64.8	48.60	1.9	46.70
STA 889+00 TO STA 890+00	48.1	36.08	0	36.08
STA 890+00 TO STA 891+00	48.1	36.08	0	36.08
STA 891+00 TO STA 892+00	48.1	36.08	0	36.08
STA 892+00 TO STA 893+00	24.1	18.08	0	18.08
TOTAL	1924.2	1443.15	709.2	733.95
PAY ITEM TOTAL	1924			

DRAINAGE SCHEDULE

STATION	CONCRETE COLLAR	REM. & REINST. CONCRETE HEADWALL FOR PIPE UNDERDRAINS	REINFORC. BARS	TRENCH BACKFILL	DRAINAGE STRUCTURE TY 1, WITH (2) TY 20 F&G	INLET TYPE B W' TY 1 FRAME OPEN LID	PIPE CULVERT CLASS A TYPE 1 24"	PIPE CULVERT REMOVAL	REMOVE INLET BOX	PLUG EXISTING SULTVERTS	PIPE CULVERT CLASS A TYPE 1 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"
	CU YD	EACH	LBS	CU YD	EACH	EACH	FOOT	FOOT	EACH	EACH	FOOT	EACH
STA 775+45 TO STA 792+65		2										
STA 780+00												
STA 792+65 TO STA 804+50												
STA 804+50 TO STA 807+33.21												
STA 885+35 TO STA 888+50												
STA 887+00 TO STA 893+25				76							800	1
STA 782+00 TO STA 790+00				5						1	277	1
STA 790+00 TO STA 792+77								48	2			
STA 785+00												
STA 788+00					1							
STA 790+00	0.48		26	3.5		1	33	18	1			
TOTAL	0.48	2	26	84.5	1	1	33	66	3	1	1077	2

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p style="text-align: center;"><b>SCHEDULES</b></p> <p>SCALE: VERT. DATE      HORIZ. DRAWN BY CHECKED BY</p>

PLOT DATE: 4/28/2005  
 FILE NAME: 66567.DWG  
 PLOT SCALE: 1"=40'  
 USER NAME: MUSENB