

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4)1	LASALLE	33	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

MAINLINE SCHEDULE

LOCATION IL 9	LENGTH	PORTLAND CEMENT CONCRETE PAVEMENT 10" JOINTED	TIE BARS #6	PORTLAND CEMENT CONCRETE SHOULDERS 10"	GEO-TECHNICAL FABRIC FOR GROUND STABILIZATION	AGG SHLDRS TY B	SUB-BASE GRANULAR MATERIAL TYPE A, 10"
	FT	SQ YD	EACH	SQ YD	SQ YD	TONS	SQ YD
LASALLE COUNTY							
STA 775+45 TO STA 776+95	150.0	0.0	120	200	250.0	22.8	250.0
STA 776+95 TO STA 777+25	30.0	21.6	24	20	51.6	4.6	51.6
STA 777+25 TO STA 783+96	671.0	2873.0	537	0	3097.0	101.9	3097.0
STA 783+96 TO STA 792+12.5	816.5	5806.0	653	0	5806.0		5806.0
STA 792+12.5 TO STA 792+65	52.5	249.8	42	0	407.3	8.0	407.3
STA 792+65 TO STA 795+65	300.0	1650.5	480	0	1850.5	91.1	1850.5
STA 795+65 TO STA 804+50	885.0	2556.6	1416	1180	4326.6	268.8	4326.6
STA 804+50 TO STA 807+33.21	283.2	818.2	227	0	912.6	43.0	912.6
South Crossover Total	3188.21	13975.7	3499	1400	16701.6	540.1	16701.6
STA 886+50 TO STA 886+70	20.0	33.3	16	0	40.0		40.0
STA 886+70 TO STA 888+50	180.0	300.0	216	200	620.0	13.7	620.0
STA 888+50 TO STA 893+25	475.0	791.6	380	0	950.0		950.0
North Crossover Total	675	1124.9	612	200	1610	13.7	1610
LINE TOTAL	3863.2	15101	4111	1600	18312	553.8	18312

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER REMOVAL	TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATOR REMOVAL	IMPACT ATTENUATOR NONREDIRECTIONAL TEST LEVEL 3
STA. TO STA.	FOOT	FOOT	EACH	EACH
SOUTH CROSSOVER				
STA 784+12 TO STA 789+62.5		812.5	1	1
NORTH CROSSOVER				
STA 886+50 TO STA 893+25	675	675		
TOTAL	675	1487.5	1	1

REMOVAL SCHEDULE

LOCATION STA TO STA	LENGTH	PCC SHLDR REMOVAL	BIT. SHLDR REMOVAL	PAV'T REMOVAL	CONCRETE BARRIER REMOVAL
	FEET	SQ YD	SQ YD	SQ YD	EACH
SOUTH CROSSOVER					
STA 775+45 TO STA 792+65	1720		2294	230	
STA 792+65 TO STA 804+50	1185		4214		
STA 804+50 TO STA 807+33.21	283.21	670			
NORTH CROSSOVER					
STA 886+50 TO STA 886+70	20		22.2		
STA 886+70 TO STA 888+50	180		500		14.4
STA 888+50 TO STA 893+25	475		792		38
TOTAL	3863.21	670	7822.2	230	52.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT.  
DATE:           HORIZ.

DRAWN BY  
CHECKED BY