

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES				ROADWAY		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000		
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	450	450		
54200640	PIPE CULVERTS, TYPE 1 CS, AA 15"	FOOT	390.0	390.0		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	30	30		
54215550	METAL END SECTIONS 15"	EACH	4	4		
60260100	INLETS TO BE ADJUSTED	EACH	3	3		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	91	91		
63500105	DELINEATORS	EACH	30	30		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	96.5	96.5		

*SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. DATE
 HORIZ. DRAWN BY
 CHECKED BY