

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES				ROADWAY		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	165	165		
* 78000100	THERMOPLASTIC PAVEMENT MARKING, - LETTERS AND SYMBOLS	SQ FT	111	111		
* 78000300	THERMOPLASTIC PAVEMENT MARKING, - LINE 5"	FOOT	1,624	1,624		
* 78000500	THERMOPLASTIC PAVEMENT MARKING, - LINE 8"	FOOT	374	374		
* 78000600	THERMOPLASTIC PAVEMENT MARKING, - LINE 12"	FOOT	164	164		
X0300626	CURB AND GUTTER REMOVAL	FOOT	75	75		
X3550500	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	SQ YD	41	41		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1,577	1,577		
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	1,051	1,051		
Z0007800	BUMPER BLOCKS	EACH	18	18		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
* X0325056	FURNISH AND INSTALL POND LINER	SQ YD	3571	3571		
* X0325057	DRILLING AND INSTALLING WATER WELL	EACH	1	1		

*SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
 DATE DATE DRAWN BY CHECKED BY