

BITUMINOUS SURFACE TREATMENT, A-3				
LOCATION	BIT. MAT. (PRIME COAT) (TON)	BIT. MAT. (COVER AND SEAL COAT) (TON)	COVER COAT AGG (TON)	SEAL COAT AGG (TON)
<u>SAND RIDGE ROAD</u> STA 20+12.33 TO STA 185+50.12	53.9	161.7	756.0	378.0
HUNTER PARKING AREA NO. 1	1.0	2.8	13.0	6.5
HUNTER PARKING AREA NO. 2	0.6	1.7	8.0	4.0
HUNTER PARKING AREA NO. 3	0.4	1.2	5.7	2.9
HUNTER PARKING AREA NO. 4	1.0	3.0	13.8	6.9
HUNTER PARKING AREA NO. 5	0.8	2.5	11.8	5.9
HUNTER PARKING AREA NO. 6	0.5	1.4	6.6	3.3
TOTAL =	58.2	174.3	814.9	407.5

PIPE CULVERT, END SECTION, DELINEATOR, & INLET SCHEDULE						
LOCATION	PIPE CULVERTS		END SEC		DELIN. S. -WHITE CRYSTAL (EACH)	ADJUST INLETS (EACH)
	TYPE 1-15 CS, AA (FOOT)	TYPE 1-18" RCCP (FOOT)	METAL 15" (EACH)	PRC FL 18" (EACH)		
	<u>SAND RIDGE ROAD &amp; HUNTER PARKING</u>					
STA 25+00		30.0		2	2	
RT STA 26+79.45	44.0					
STA 35+00		30.0		2	2	
RT STA 42+00	49.0					
STA 43+00		30.0		2	2	
LT STA 43+36.16	48.0					
LT STA 54+76.53	44.0					
RT STA 56+56.32	50.0		2			
STA 57+00		30.0		2	2	
STA 67+00		30.0		2	2	
STA 78+00		30.0		2	2	
LT STA 79+01.66	50.0					
RT STA 82+28.77	55.0					
STA 89+00		30.0		2	2	
STA 95+00		30.0		2	2	
STA 101+00		30.0		2	2	
STA 110+00		30.0		2	2	
STA 116+00		30.0		2	2	
STA 121+00		30.0		2	2	
RT STA 121+76.00	50.0		2			
STA 135+00		30.0		2	2	
STA 145+00		30.0		2	2	
STA 176+70		30.0		2	2	
<u>JAKE WOLF FISH HATCHERY PARKING AREA</u>						
STA. 5+16.17 @ 27.85' LT						1
STA. 5+93.04 @ 26.09' RT						1
STA. 6+84.74 @ 25.41' RT						1
TOTAL =	390.0	450.0	4	30	30	3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 SCALE: VERT.      DRAWN BY  
           HORIZ.      CHECKED BY  
 DATE