

SIGNING SCHEDULE

LOCATION: SIGNS SHALL BE LOCATED AT THE FOLLOWING INTERSECTIONS IN CONJUNCTION WITH THE SIGN LOCATIONS MAP.	MUTCD NO.	MESSAGE	SIZE IN x IN	SIGN PANELS T-1 (SQ FT)	TELE. SIGN SUPPORT (FOOT)
1. GOOFY RIDGE BLACKTOP AND SAND RIDGE RD.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
2. GOOFY RIDGE BLACKTOP AND PINE VALLEY DR.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
3. GOOFY RIDGE BLACKTOP AND CACTUS DR.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
4. SAND RIDGE RD. EAST ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
5. FOREST CITY RD. (TR 13) EAST ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
6. BISHOP RD. (TR 134) AND SOUTH ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
SAND RIDGE ROAD LT STA 20+65.00	R1-1(3030)	STOP	30 x 30	6.25	15.0
LT STA 28+00.00	W3-1a(3030)	STOP AHEAD	30 x 30	6.25	15.0
JAKE WOLF FISH HATCHERY RT STA 4+16.01 RT STA 4+16.01	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
RT STA 4+37.26 RT STA 4+37.26	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
RT STA 4+53.32 RT STA 4+53.32	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
TOTAL =				96.50	165.0

NOTES: ALL POST UNLESS OTHERWISE NOTED SHALL MEET THE REQUIREMENTS OF SECTION 728 OF THE STANDARD SPECIFICATIONS. EACH POST SHALL ALSO INCLUDE A 2 1/4" x 2 1/4" x 4' BASE DRIVEN INTO THE GROUND EXCEPT THE LAST 2".

ALL POST SHALL BE OFFSET FROM EDGE OF THE PAVEMENT BY 18'. SEE STANDARD DRAWINGS FOR POST IN PAVEMENT.

PAVEMENT MARKING SCHEDULE

LOCATION	THERMO. PAVT. MK LINE 5" (YELLOW) (FOOT)	THERMO. PAVT. MK. LINE 8" (YELLOW) (FOOT)	THERMO. PAVT. MK. LINE 12" (WHITE) (FOOT)	THERMO. PAVT. MK. L & S (WHITE) (SQ FT)
JAKE WOLF FISH HATCHERY PARKING AREA STA 1+25.06 TO STA 10+85.44	1624	374	164	111.3
TOTAL =	1624	374	164	111
NOTE: LETTERS & SYMBOLS SMALL DIRECTIONAL ARROW = 6.5 SQ FT HANDICAP SYMBOL = 4.6 SQ FT				

BUMPER BLOCK SCHEDULE (INCIDENTAL TO EARTH EXC.)

PARKING AREAS	BUMPER BLOCK REMOVAL (EACH)	BUMPER BLOCK (NEW) (EACH)
JAKE WOLF FISH HATCHERY VISITOR PARKING	18	18
TOTAL =	18	18

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY