

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE FOOO TOTAL QTY
X0324633	BITUMINOUS SURFACE TREATMENTS (PREVENTIVE MAINTENANCE)	SQ YD	37,383
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.7
40600300	AGGREGATE (PRIME COAT)	TON	56.1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	74
40600990	TEMPORARY RAMP	SQ YD	13
48101200	AGGREGATE SHOULDERS, TYPE B	TON	630
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,620
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	540
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	4,050
78100215	TEMPORARY FLEXIBLE PAVEMENT MARKER	EACH	810
X4066765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE, N50	TON	1,570

\*SPECIALTY ITEM

Rev.

INDEX / STDS / SIGNATURES  
FAU 1768 (I-55 E FRONTAGE RD)  
SECTION (86-2)Q-2  
MONTGOMERY COUNTY