

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	3BS-6,4BS-7	ADAMS	6	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODED NO.	ITEM	UNIT	100% STATE
			I000 TOTAL QUANTITY
35800100	PREPARATION OF BASE	SQ YD	30
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.5
40600300	AGGREGATE (PRIME COAT)	TON	44.7
40600895	CONSTRUCTION TEST STRIP	EACH	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	27.8
40600990	TEMPORARY RAMP	SQ YD	22.8
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	22354
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	100
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	300
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	300
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	120
48101200	AGGREGATE SHOULDERS, TYPE B	TON	614
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	2409
7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	803
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	22298
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1874
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	937
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE N50	TON	14

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUNATITIES
FAP 317 (US 24)
ADAMS COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE