

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	3RS-6;4RS-7	ADAMS	6	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STRIPING SCHEDULE	
LOCATION	PAINT PAVEMENT MARKING - LINE 5" (LIN FT)
WHITE EDGE LINE	16060
YELLOW SKIP DASH	
1255+85 to 1261+84	150
1263+97 to 1271+18	180
1271+30 to 1330+52	1481
1331+94 to 1336+15	105
YELLOW NO PASSING ZONE	
(WB) 1255+85 to 1263+97	812
(EB) 1261+84 to 1271+30	606
(WB) 1271+18 to 1277+24	763
(EB) 1279+20 to 1285+52	946
(WB) 1324+31 to 1331+94	632
(EB) 1330+52 to 1336+15	563
TOTAL	22298

SIDEROADS, ENTRANCE SCHEDULE							
LOCATION	TYPE	SURFACE TYPE	AGG, SHLD, TYPE B (TONS)	INCIDENTAL BIT. SURF. (TONS)	BIT. MAT. (PR CT) (TONS)	BIT. SURF. REMOVAL (SQ YD)	PREPARATION OF BASE (SY YD)
1261+00 +/- LT	CE	BIT		2	0.005	14	
1281+00 +/- LT	PE	AGG	1	2	0.02		11
1288+00 +/- RT	FE	EARTH	1				
1303+00 +/- LT	PE	AGG	1	2	0.02		11
1308+65 +/- LT	FE	AGG	1				
1317+00 +/- LT	SR	BIT		3	0.006	17	
1317+00 +/- RT	SR	AGG		2	0.01		8
1319+00 +/- LT	PE	BIT		1	0.003	7	
1325+00 +/- LT	PE	BIT		2	0.004	10	
TOTALS			4	14	1	48	30

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SIDEROAD, ENTRANCE SCHEDULE
 & STRIPING SCHEDULE
 FAP 317 (US 24)
 ADAMS COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____