

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1419	04-00239-00-	COOK	34	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

83792

LOCATION OF WORK				FAU ROUTE 1419 (MADISON STREET) @							
SUMMARY OF QUANTITIES				CONSTRUCTION CODE	Y031-1F ₁	Y031-1F ₂	Y031-1F ₃	Y031-1F ₄	Y031-1F ₅	Y031-1F ₆	Y031-1F ₇
SP	CODE NO.	ITEM	UNIT	TOTAL	WISCONSIN AVE.	HOME AVE.	OAK PARK AVE.	EAST AVE.	RIDGELAND AVE.	LOMBARD AVE.	INTERCONNECT
	67100100	MOBILIZATION	L. SUM	1							1
*	70102625	TRAFFIC CONTROL AND PROTECTION STANDARD 701606	L. SUM	1	0.15	0.15	0.15	0.15	0.15	0.15	0.1
*	70102630	TRAFFIC CONTROL AND PROTECTION STANDARD 701601	L. SUM	1	0.15	0.15	0.15	0.15	0.15	0.15	0.1
*	70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L. SUM	1	0.15	0.15	0.15	0.15	0.15	0.15	0.1
*	70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L. SUM	1	0.15	0.15	0.15	0.15	0.15	0.15	0.1
	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FT	5235		173		357	166		4539
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FT	304		104		68	72	60	
	81400100	HANDHOLE	EACH	6							6
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6	1	1	1	1	1	1	
	85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	2				1		1	
	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2							2
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	320		320					
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FT	3253	677	592		660	647	677	
	87900200	DRILL EXISTING HANDHOLE	EACH	62	2	8	8	14	12	10	8
	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	32	4	4		8	8	8	
	88500100	INDUCTIVE LOOP DETECTOR	EACH	10	2	2		2	2	2	
	88600100	DETECTOR LOOP, TYPE I	FT	1673	152	152	341	350	346	332	
	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5	1	1		1	1	1	
	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO 14/1C	FOOT	6342							6342
	X8800020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	24	4	4		6	4	6	
	X8800035	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	16	6	6		2		2	
	X8800040	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	8				2	4	2	
	X8800045	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	8				2	4	2	
	X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	26	6			8	4	8	
	X8810620	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	7	1	4			2		
*	XX004980	REOPTIMIZE TRAFFIC SIGNAL SYSTEM	L. SUM	1							1
	XX003660	FIBER OPTIC CABLE IN CONDUIT NO. 62.5/125 MM24F SM 12F	FT	6342							6342
	Z0013798	CONSTRUCTION LAYOUT	L. SUM	1							1

TIME: 09:50:09 AM

DATE: 06/06/2005

FILENAME: s:\@SAV\751-400\784\432\micro\Strand\Strand\S00.dgn



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE		
		MADISON STREET CMAO	
		SUMMARY OF QUANTITIES	
		SCALE: VERT. NONE	DRAWN BY RCB
		HORIZ.	CHECKED BY RKK
		DATE 06/06/2005	