

FILE #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH	A47	LAKE	176	7
STA.	TO STA.			
03-00088-00-PP	ILLINOIS	SURFACE TRANSPORTATION FUNDING		
CONTRACT NUMBER 83807				

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
Deerfield Parkway, Buffalo Grove Road, Highland Grove Drive													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
15+26	24	0	0	0	0	56	8	8	11	1,343	194	194	266
15+50	50	111	16	16	22	108	15	15	23	5,375	750	750	1,125
16+00	50	104	14	14	23	110	16	16	24	5,475	775	775	1,175
16+50	50	115	17	17	24	106	19	19	23	5,300	950	950	1,150
17+00	50	97	21	21	22	99	21	21	22	4,950	1,025	1,025	1,100
17+50	50	101	20	20	22	100	22	22	20	5,000	1,075	1,075	1,000
18+00	50	99	23	23	18	99	23	23	22	4,925	1,150	1,150	1,100
18+50	50	98	23	23	26	94	25	25	24	4,675	1,225	1,225	1,175
19+00	50	89	26	26	21	87	21	21	17	4,325	1,025	1,025	825
19+50	50	84	15	15	12	96	8	8	6	4,775	375	375	300
20+00	50	107	0	0	0	101	13	13	12	5,050	650	650	600
20+50	50	95	26	26	24	90	24	33	34	4,475	1,175	1,625	1,700
21+00	50	84	21	39	44	85	21	39	41	4,225	1,050	1,925	2,050
21+50	50	85	21	38	38	85	22	37	40	4,225	1,100	1,825	2,000
22+00	50	84	23	35	42	83	24	35	44	4,125	1,175	1,750	2,175
22+50	50	81	24	35	45	78	26	35	47	3,900	1,300	1,725	2,325
23+00	50	75	28	34	48	75	30	35	49	3,750	1,475	1,750	2,425
23+50	50	75	31	36	49	75	33	37	54	3,725	1,625	1,850	2,700
24+00	50	74	34	38	59	74	37	39	60	3,675	1,825	1,950	2,975
24+50	50	73	39	40	60	64	62	63	51	3,175	3,100	3,150	2,550
25+00	50	54	85	86	42	47	43	52	37	2,325	2,125	2,600	1,825
25+50	50	39	0	18	31	48	0	16	25	2,375	0	800	1,225
26+00	50	56	0	14	18	62	0	12	13	3,100	0	575	625
26+50	50	68	0	9	7	68	0	8	7	3,375	0	400	350
27+00	50	67	0	7	7	59	0	7	8	2,950	0	350	375
27+50	50	51	0	7	8	58	0	10	8	2,875	0	475	375
28+00	50	64	0	12	7	69	0	11	9	3,425	0	550	425
28+50	50	73	0	10	10	68	0	7	23	3,400	0	350	1,125
29+00	50	63	0	4	35	73	0	2	39	3,625	0	100	1,925
29+50	50	82	0	0	42	86	0	0	37	4,275	0	0	1,850
30+00	50	89	0	0	32	83	0	0	26	4,125	0	0	1,300
30+50	50	76	0	0	20	72	0	0	18	3,600	0	0	875

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE
SCHEDULE OF QUANTITIES
DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM