

ITE.#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH	A47	LAKE	176	10
STA.		TO STA.		
03-00088-00-FP		ILLINOIS	SURFACE TRANSPORTATION FUNDING	
CONTRACT NUMBER 83807				

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
Deerfield Parkway, Buffalo Grove Road, Highland Grove Drive													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
61+00	50	49	0	11	38	56	23	35	43	2,800	1,125	1,725	2,150
61+50	50	63	45	58	48	63	50	40	41	3,150	2,500	2,000	2,050
62+00	50	63	55	22	34	63	48	40	35	3,125	2,375	2,000	1,725
62+50	50	62	40	58	35	71	42	61	37	3,525	2,100	3,050	1,850
63+00	50	79	44	64	39	85	42	56	37	4,250	2,075	2,775	1,850
63+50	50	91	39	47	35	97	20	24	35	4,825	975	1,175	1,750
64+00	50	102	0	0	35	107	0	0	31	5,325	0	0	1,525
64+50	50	111	0	0	26	129	0	0	25	6,425	0	0	1,225
65+00	50	146	0	0	23	148	18	18	28	7,400	900	900	1,375
65+50	50	150	36	36	32	147	37	37	30	7,350	1,850	1,850	1,500
66+00	50	144	38	38	28	138	38	38	25	6,875	1,900	1,900	1,250
66+50	50	131	38	38	22	124	38	38	21	6,175	1,900	1,900	1,050
67+00	50	116	38	38	20	116	38	38	20	5,800	1,900	1,900	1,000
67+50	50	116	38	38	20	91	19	19	17	4,525	950	950	825
68+00	50	65	0	0	13	73	0	0	11	3,650	0	0	525
68+50	50	81	0	0	8	76	0	0	11	3,800	0	0	525
69+00	50	71	0	0	13	74	0	0	13	3,700	0	0	625
69+50	50	77	0	0	12	78	0	0	12	3,900	0	0	600
70+00	50	79	0	0	12	84	19	19	15	4,175	950	950	750
70+50	50	88	38	38	18	83	38	38	17	4,125	1,900	1,900	825
71+00	50	77	38	38	15	74	38	38	16	3,675	1,900	1,900	800
71+50	50	70	38	38	17	68	38	38	16	3,375	1,900	1,900	800
72+00	50	65	38	38	15	70	19	19	13	3,500	950	950	650
72+50	50	75	0	0	11	74	0	0	9	3,700	0	0	450
73+00	50	73	0	0	7	94	0	0	7	4,675	0	0	350
73+50	1	114	0	0	7	57	0	0	4	57	0	0	4
73+51		0	0	0	0								
SUBTOTAL DEERFIELD PARKWAY										488,675	73,044	85,644	127,295

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE
SCHEDULE OF QUANTITIES
DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM