

FILE #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH	A47	LAKE	176	11
STA.	TO STA.			
03-00088-00-PP	ILLINOIS	SURFACE TRANSPORTATION FUNDING		
CONTRACT NUMBER 83807				

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
Deerfield Parkway, Buffalo Grove Road, Highland Grove Drive													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
109+24		0	0	0	0								
	26					6	0	0	1	156	0	0	13
109+50		12	0	0	1	13	0	0	1	650	0	0	50
	50					13	0	0	2	650	0	0	75
110+00		14	0	0	1	13	0	0	3	600	0	0	150
	50					12	0	0	3	600	0	0	150
110+50		12	0	0	2	12	0	0	3	600	0	0	150
	50					12	0	0	3	600	0	0	150
111+00		12	0	0	4	14	0	0	5	675	0	0	225
	50					14	0	0	5	675	0	0	225
111+50		15	0	0	5	17	0	0	4	825	0	0	175
	50					17	0	0	4	825	0	0	175
112+00		18	0	0	2	20	0	0	2	1,000	0	0	100
	50					20	0	0	2	1,000	0	0	100
112+50		22	0	0	2	24	0	0	3	1,200	0	0	150
	50					24	0	0	3	1,200	0	0	150
113+00		26	0	0	4	25	0	0	4	1,225	0	0	200
	50					25	0	0	4	1,225	0	0	200
113+50		23	0	0	4	23	0	0	2	1,125	0	0	100
	50					23	0	0	2	1,125	0	0	100
114+00		22	0	0	0	24	0	0	2	1,175	0	0	100
	50					24	0	0	2	1,175	0	0	100
114+50		25	0	0	4	31	0	0	4	1,525	0	0	175
	50					31	0	0	4	1,525	0	0	175
115+00		36	0	0	3	36	0	0	3	1,800	0	0	150
	50					36	0	0	3	1,800	0	0	150
115+50		36	0	0	3	37	0	0	3	1,825	0	0	150
	50					37	0	0	3	1,825	0	0	150
116+00		37	0	0	3	36	0	0	3	1,800	0	0	150
	50					36	0	0	3	1,800	0	0	150
116+50		35	0	0	3	36	3	3	4	1,775	150	150	200
	50					36	3	3	4	1,775	150	150	200
117+00		36	6	6	5	35	6	6	5	1,750	300	300	250
	50					35	6	6	5	1,750	300	300	250
117+50		34	6	6	5	31	6	6	5	1,525	300	300	250
	50					31	6	6	5	1,525	300	300	250
118+00		27	6	6	5	23	6	8	6	1,150	275	375	300
	50					23	6	8	6	1,150	275	375	300
118+50		19	5	9	7	19	6	8	7	925	275	375	325
	50					19	6	8	7	925	275	375	325
119+00		18	6	6	6	56	3	5	3	2,800	150	225	150
	50					56	3	5	3	2,800	150	225	150
119+50		94	0	3	0	47	0	2	0	47	0	2	0
	1					47	0	2	0	47	0	2	0
119+51		0	0	0	0	0	0	0	0	0	0	0	0
	98					0	0	0	0	0	0	0	0
120+49		0	0	0	0	50	0	1	0	50	0	1	0
	1					50	0	1	0	50	0	1	0
120+50		100	0	2	0	58	9	10	8	2,875	450	500	400
	50					58	9	10	8	2,875	450	500	400
121+00		15	18	18	16	39	18	18	16	1,950	900	900	800
	50					39	18	18	16	1,950	900	900	800
121+50		63	18	18	16	63	18	18	17	3,125	900	900	850
	50					63	18	18	17	3,125	900	900	850
122+00		62	18	18	18	63	18	18	19	3,150	900	900	925
	50					63	18	18	19	3,150	900	900	925
122+50		64	18	18	19	67	18	18	20	3,325	900	900	1,000
	50					67	18	18	20	3,325	900	900	1,000
123+00		69	18	18	21	65	18	18	21	3,250	900	900	1,025
	50					65	18	18	21	3,250	900	900	1,025
123+50		61	18	18	20	61	18	18	20	3,050	900	900	1,000
	50					61	18	18	20	3,050	900	900	1,000
124+00		61	18	18	20	70	18	18	18	3,475	900	900	900
	50					70	18	18	18	3,475	900	900	900

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE
SCHEDULE OF QUANTITIES
DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM