

FILE #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
CH	A47	LAKE	176	14
STA.		TO STA.		
03-00088-00-PP		LINKS	SURFACE TRANSPORTATION FUNDING	
CONTRACT NUMBER 83807				

SCHEDULE OF PORTLAND CEMENT CONC. DRIVEWAY PAVEMENT DEERFIELD PARKWAY				
STATION		42300200 PORT. CEMENT CONC. DRIVEWAY PVMT. 6"	42300400 PORT. CEMENT CONC. DRIVEWAY PVMT. 8"	
FROM	TO	SQ. YD.	SQ. YD.	
15+26	18+00	0	0	
18+00	23+00	0	0	
23+00	27+50	0	0	
27+50	33+00	0	0	
33+00	38+00	0	0	
38+00	43+00	0	0	
43+00	48+00	0	0	
48+00	53+00	0	0	
53+00	57+00	0	0	
57+00	62+25	0	119	
62+25	67+00	92	0	
67+00	72+00	0	0	
72+00	73+50	0	0	
DEERFIELD PARKWAY SUBTOTAL		92	119	
109+24	113+00	0	0	
113+00	119+00	0	0	
119+00	121+00	0	0	
121+00	127+00	0	0	
127+00	131+04	0	0	
BUFFALO GROVE RD SUBTOTAL		0	0	
905+64	911+00	89	0	
911+00	914+00	80	0	
914+00	916+00	0	0	
HIGHLAND GROVE DR SUBTOTAL		169	0	
PROJECT TOTAL		261	119	

SCHEDULE OF COMB. CONC. CURB & GUTTER REMOVAL DEERFIELD PARKWAY			
STATION		44000500 COMB. C & G REMOVAL	
FROM	TO	(LINEAL FOOT)	
15+26	18+00	350	
18+00	23+00	180	
23+00	27+50	0	
27+50	33+00	150	
33+00	38+00	90	
38+00	43+00	0	
43+00	48+00	413	
48+00	53+00	0	
53+00	57+00	0	
57+00	62+25	400	
62+25	67+00	280	
67+00	72+00	685	
72+00	73+50	300	
S.O.C. STAGE3 WEST END		0	
S.O.C. STAGE3 EAST END		0	
DEERFIELD PARKWAY SUBTOTAL		2,848	
109+24	113+00	123	
113+00	119+00	120	
119+00	121+00	35	
121+00	127+00	240	
127+00	131+04	0	
BUFFALO GROVE RD SUBTOTAL		518	
905+64	911+00	600	
911+00	914+00	200	
914+00	916+00	525	
HIGHLAND GROVE DR SUBTOTAL		1,325	
PROJECT TOTAL		4,691	

SCHEDULE OF COMB. CONC. CURB & GUTTER DEERFIELD PARKWAY				
STATION		(60605000) COMB. C & G TY B-6.24 (LINEAL FOOT)	(60603800) COMB. C & G TY B-6.12 (LINEAL FOOT)	X6063401 COMB. C&G TY M4.12 (LINEAL FOOT)
FROM	TO			
15+26	18+00	491	0	0
18+00	23+00	1,010	292	0
23+00	27+50	900	639	0
27+50	33+00	1,125	451	0
33+00	38+00	875	0	0
38+00	43+00	1,000	408	0
43+00	48+00	1,038	301	0
48+00	53+00	1,000	686	0
53+00	57+00	800	575	0
57+00	62+25	1,100	76	0
62+25	67+00	950	687	0
67+00	72+00	1,050	230	0
72+00	73+50	300	302	0
S.O.C. STAGE3 WEST END		0	412	0
S.O.C. STAGE3 EAST END		0	0	0
DEERFIELD PARKWAY SUBTOTAL		11,639	5,059	0
109+24	113+00	21	0	0
113+00	119+00	600	0	0
119+00	121+00	160	0	0
121+00	127+00	1,200	222	0
127+00	131+04	808	0	0
BUFFALO GROVE RD SUBTOTAL		2,789	222	0
905+64	911+00	0	0	550
911+00	914+00	0	0	45
914+00	916+00	0	0	490
HIGHLAND GROVE DR SUBTOTAL		0	0	1,085
PROJECT TOTAL		14,428	5,281	1,085

SCHEDULE OF DRIVEWAY PAVEMENT REMOVAL DEERFIELD PARKWAY		
STATION		44000200 DRIVEWAY PAVEMENT REMOVAL SQ. YD.
FROM	TO	
15+26	18+00	0
18+00	23+00	0
23+00	27+50	0
27+50	33+00	0
33+00	38+00	60
38+00	43+00	68
43+00	48+00	187
48+00	53+00	0
53+00	57+00	0
57+00	62+25	137
62+25	67+00	83
67+00	72+00	0
72+00	73+50	0
DEERFIELD PARKWAY SUBTOTAL		535
109+24	113+00	0
113+00	119+00	0
119+00	121+00	0
121+00	127+00	0
127+00	131+04	0
BUFFALO GROVE RD SUBTOTAL		0
905+64	911+00	105
911+00	914+00	0
914+00	916+00	105
HIGHLAND GROVE DR SUBTOTAL		210
PROJECT TOTAL		745

SCHEDULE OF CONC. MEDIAN DEERFIELD PARKWAY		
STATION		X4403300 CONC. MEDIAN REMOVAL SQ. FT.
FROM	TO	
15+26	18+00	973
18+00	23+00	0
23+00	27+50	0
27+50	33+00	0
33+00	38+00	0
38+00	43+00	0
43+00	48+00	0
48+00	53+00	0
53+00	57+00	0
57+00	62+25	0
62+25	67+00	0
67+00	72+00	0
72+00	73+50	0
S.O.C. STAGE3 WEST END		740
S.O.C. STAGE3 EAST END		2,590
DEERFIELD PARKWAY SUBTOTAL		4,303
109+24	113+00	0
113+00	119+00	0
119+00	121+00	130
121+00	127+00	1,966
127+00	131+04	0
BUFFALO GROVE RD SUBTOTAL		2,096
905+64	911+00	0
911+00	914+00	0
914+00	916+00	0
HIGHLAND GROVE DR SUBTOTAL		0
PROJECT TOTAL		6,399

SCHEDULE OF CONC. MEDIAN DEERFIELD PARKWAY				
STATION		60619600 CONC. MEDIAN TYPE SB-6.12 SQ. FT.	60622000 CONC. MEDIAN TYPE SM-2.12 SQ. FT.	606246 CORRUGATED MEDIAN
FROM	TO			
15+26	18+00	1,098	0	0
18+00	23+00	915	0	100
23+00	27+50	610	0	0
27+50	33+00	950	0	140
33+00	38+00	1,340	0	100
38+00	43+00	1,260	0	0
43+00	48+00	1,000	0	100
48+00	53+00	715	0	0
53+00	57+00	540	0	0
57+00	62+25	1,260	0	150
62+25	67+00	250	0	0
67+00	72+00	1,090	0	100
72+00	73+50	0	0	0
S.O.C. STAGE3 WEST END		760	0	0
S.O.C. STAGE3 EAST END		650	0	0
DEERFIELD PARKWAY SUBTOTAL		12,438	0	690
109+24	113+00	0	0	0
113+00	119+00	0	0	0
119+00	121+00	0	0	100
121+00	127+00	0	870	0
127+00	131+04	0	0	0
BUFFALO GROVE RD SUBTOTAL		0	870	100
905+64	911+00	0	0	0
911+00	914+00	0	0	0
914+00	916+00	0	0	0
HIGHLAND GROVE DR SUBTOTAL		0	0	0
PROJECT TOTAL		12,438	870	790

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE

SCHEDULE OF QUANTITIES DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM

**BID SET
BID SET**