

CODE NO.	ITEM	UNIT	TOTAL QTY	(IN CONTRACT) BY CONTRACTOR 1000-2A	(NOT IN CONTRACT) BY COUNTY
20200100	EARTH EXCAVATION	CU YD	2,521	2,521	
20400800	FURNISHED EXCAVATION	CU YD	3,152	3,152	
20800150	TRENCH BACKFILL	CU YD	204		204
* 25000200	SEEDING, CLASS 2	ACRE	4.5	4.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405	405	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405	405	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405	405	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	9	9	
* 25002300	TEMPORARY SEEDING	ACRE	4.5	4.5	
* 25100115	MULCH, METHOD 2	ACRE	9.0	9.0	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450	450	
* 28000300	TEMPORARY DITCH CHECKS	EACH	35	35	
* 28000400	PERIMETER EROSION BARRIER	FOOT	440	440	
* 28000500	INLET AND PIPE PROTECTION	EACH	35	35	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	297	297	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	511	511	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	5,395	5,395	
40600300	AGGREGATE (PRIME COAT)	TON	119	119	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	128	128	
40600990	TEMPORARY RAMP	SQ YD	285	285	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GAL	395	395	
40800030	AGGREGATE (PRIME COAT)	TON	2	2	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	170	170	
42001300	PROTECTIVE COAT	SQ YD	98	98	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	98	98	
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ YD	537	537	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	98	98	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	24		24
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	83		83
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	68		68
* 44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	44,260	44,260	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,550	1,550	
54020402	PRECAST CONCRETE BOX CULVERT 4' X 2' (M273)	FOOT	144		144
	PRECAST CONCRETE BOX CULVERT END SECTIONS 4' X 2'	EACH	8		8
54020802	PRECAST CONCRETE BOX CULVERT 8' X 2' (M273)	FOOT	62		62
	PRECAST CONCRETE BOX CULVERT END SECTIONS 8' X 2'	EACH	2		2
54207159	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	80		80
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2		2
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	6		6
54215550	METAL END SECTIONS 15"	EACH	28		28
54215553	METAL END SECTIONS 18"	EACH	12		12
54215556	METAL END SECTIONS 21"	EACH	6		6
54215559	METAL END SECTIONS 24"	EACH	4		4
54215565	METAL END SECTIONS 30"	EACH	4		4
54215760	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	8		8
54215766	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 21"	EACH	2		2
54215775	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	4		4
54215781	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	2		2


CODE NO.	ITEM	UNIT	TOTAL QTY	(IN CONTRACT) BY CONTRACTOR 1000-2A	(NOT IN CONTRACT) BY COUNTY
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	28		28
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	518		518
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	222		222
542D0226	PIPE CULVERTS, CLASS D, TYPE 1 21"	FOOT	122		122
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	68		68
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	66		66
542D5470	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 15"	FOOT	108		108
542D5476	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 21"	FOOT	26		26
542D5485	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 30"	FOOT	71		71
542D5491	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 36"	FOOT	34		34
60603400	GUTTER OUTLET (SPECIAL)	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	1	
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
* 70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12	
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,000	3,000	
* 70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	33,125	33,125	
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	33,125	33,125	
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	1,500	1,500	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	7,405	7,405	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	2,800	2,800	
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	35	35	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	4,050	4,050	

\* = SPECIALTY ITEM

**CRAWFORD COUNTY  
FAS ROUTE 694  
MFT SECTION 03-00088-00-WR**

**SUMMARY OF QUANTITIES**

DRAWN BY MAL	FILE NO. 24-7263
DATE 12/29/04	BOOK NO. 2646
CHECKED BY ERB	SHEET NO. 2 OF 56


**Farnsworth GROUP**  
 200 N. 300. ST., Suite 206  
 Effingham, IL 62401  
 217/342-9988, 217/342-8888 fax