

**PIPE CULVERTS SCHEDULE (BY COUNTY STAFF)**

STATION LOCATION	ALUMINIZED - CLASS D TYPE 1 (FOOT)									RCCP - CLASS A TYPE 1 (FOOT)		
	15"	15" ERS	18"	21"	21" ERS	24"	30"	30" ERS	36" ERS	24"	24" ELLIP, ERS	
14+76.95					26							
16+67.69				48								
17+76.31				32								
19+21.42											22	
20+38.49											22	
21+45.79											36	
22+46.66										28		
22+86.70						32	30					
23+51.65												
24+25.42				36								
25+11.95				38								
27+11.07				36								
29+16.74	48											
30+74.61	30											
32+39.33	24											
39+57.73	ACROSS ROAD							41				
45+54.78	RT	24										
46+61.10	RT	24										
49+92.04	RT	60										
53+01.69	LT			38								
65+13.25	RT	60										
76+86.47	LT				42							
85+09.15	LT	34										
85+09.96	RT	36										
103+74.30	RT	36										
110+80.05	LT	36										
116+05.61	RT	38										
118+48.46	LT	36										
119+64.49	LT	36										
124+82.51	LT	36										
128+45.33	RT	36										
128+54.75	LT	32										
134+32.29	RT			36								
134+34.39	LT			38								
142+16.11	LT								34			
143+03.47	RT						36					
148+76.91	LT							30				
151+41.00	RT					36						
TOTALS		518	108	222	122	26	68	66	71	34	28	80

**PIPE CULVERT END SECTIONS SCHEDULE (BY COUNTY STAFF)**

STATION LOCATION	ALUMINIZED - METAL END SECTIONS (EACH)									PRECAST REINF. CONCRETE FLARED END SECTIONS (EACH)	
	15"	15" ERS	18"	21"	21" ERS	24"	30"	30" ERS	36" ERS	24"	24" ELLIP, ERS
14+76.95					2						
16+67.69					2						
17+76.31					2						
19+21.42											2
20+38.49											2
21+45.79											2
22+46.66										2	
22+86.70						2	2				
23+51.65											
24+25.42				2							
25+11.95				2							
27+11.07				2							
29+16.74	2										
30+74.61	2										
32+39.33	2										
39+57.73	ACROSS ROAD							2			
45+54.78	RT	2									
46+61.10	RT	2									
49+92.04	RT	4									
53+01.69	LT			2							
65+13.25	RT	2									
76+86.47	LT				2						
85+09.15	LT	2									
85+09.96	RT	2									
103+74.30	RT	2									
110+80.05	LT	2									
116+05.61	RT	2									
118+48.46	LT	2									
119+64.49	LT	2									
124+82.51	LT	2									
128+45.33	RT	2									
128+54.75	LT	2									
134+32.29	RT			2							
134+34.39	LT			2							
142+16.11	LT								2		
143+03.47	RT						2				
148+76.91	LT							2			
151+41.00	RT					2					
TOTALS		28	8	12	6	2	4	4	4	2	6

**PRECAST CONCRETE BOX CULVERT AND PRECAST END SECTIONS SCHEDULE (BY COUNTY STAFF)**

STATION LOCATION	4' X 2' BOX (FOOT)	4' X 2' END SECTION (EACH)	8' X 2' BOX (FOOT)	8' X 2' END SECTION (EACH)
56+71.13	ACROSS ROAD	36	2	
76+34.54	ACROSS ROAD		62	2
93+27.00	ACROSS ROAD	36	2	
114+07.50	ACROSS ROAD	36	2	
157+16.04	ACROSS ROAD RT	36	2	
TOTALS	144	8	62	2

**CLASS D PATCHES 9 INCH AND TRENCH BACKFILL SCHEDULE (BY COUNTY STAFF)**

STATION LOCATION	TRENCH BACKFILL (CU YD)	CLASS D PATCH, 9" TYPE II (SQ YD)	CLASS D PATCH, 9" TYPE III (SQ YD)	CLASS D PATCH, 9" TYPE IV (SQ YD)
39+57.73	5	11		
49+92.04 RT	6	13		
56+71.13	19		20	
76+34.54	51			39
76+34.49	67			29
93+27	19		20	
114+07.50	18		20	
157+16.04, 133' RT	19		23	
TOTAL	204	24	83	68

SCHEDULE TABLES FOR WORK TO BE COMPLETED BY COUNTY STAFF ARE SHOWN ON THIS SHEET FOR INFORMATION ONLY. THESE ITEMS WILL BE COMPLETED BY COUNTY STAFF PRIOR TO THE CONTRACTOR STARTING THE CONTRACT WORK.

CRAWFORD COUNTY  
FAS ROUTE 694  
MFT SECTION 03-00088-00-WR

**SCHEDULE OF QUANTITIES**