

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	31-1-2, 31B	SALINE	199	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	COUNTY: SALINE					
		LOCATION:					
		CONSTRUCTION TYPE CODE:					
		FUNDING:					
		UNIT	TOTAL QUANTITY	RURAL	FED 80% STATE 20% ROAD	FED 80% STATE 20% TRAFFIC SIGNAL	FED 80% STATE 20% CULVERT SN 083-2014
72000100	SIGN PANEL - TYPE 1	SQ FT	76			76	
X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ FT	1305		1305		
78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	18783		18783		
78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	1315		1315		
X7800540	POLYUREA PAVEMENT MARKING TYPE II - LINE 8" (SPECIAL)	FOOT	511		511		
X7800550	POLYUREA PAVEMENT MARKING TYPE II - LINE 12" (SPECIAL)	FOOT	619		619		
X7800580	POLYUREA PAVEMENT MARKING TYPE II - LINE 24" (SPECIAL)	FOOT	188		188		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	544		544		
78300105	PAVEMENT MARKING REMOVAL	FOOT	700		700		
80300100	LOCATING UNDERGROUND CABLE	FOOT	1310			1310	
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1				
81012500	CONDUIT IN TRENCH, 1/2" DIA., PVC	FOOT	832			832	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	30			30	
81021540	CONDUIT, AUGERED 1/2" DIA., PVC	FOOT	170			170	
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	509			509	
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	212			212	
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	85			85	
81400400	CONCRETE HANDHOLE	EACH	8			8	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1307			1307	
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10	FOOT	1278			1278	
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1			1	
8300000	POLE FOUNDATION, METAL, 6" DIA., 3' LONG	EACH	1				
8400000	REMOVAL OF POLE FOUNDATION, CONCRETE	EACH	1				
8400000	REMOVE AND RELOCATE EXISTING LIGHTING UNIT	EACH	1				
85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1	
86600010	GULFBOX JUNCTION	EACH	7			7	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1889			1889	
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	743			743	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD - IN, NO. 14 1 PAIR	FOOT	4353			4353	
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2			2	
87700220	STEEL FOUNDATION MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12			12	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5	
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	60			60	
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8			8	
88500100	INDUCTIVE LOOP DETECTOR	EACH	12			12	
88500200	INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT	EACH	6			6	
88600100	DETECTOR LOOP, TYPE I	FOOT	1656			1656	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
X0300739	UNINTERRUPTIBLE POWER SUPPLY	EACH	1			1	
XX005096	TRENCH FRAMES AND GRATES	FOOT	32		32		
X0321156	HIGH VISIBILITY TEMPORARY FENCING	FOOT	279		279		
X0322729	MATERIAL TRANSFER DEVICE	TON	7052		7052		
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	13900		13900		
X0323310	REMOVAL OF EXISTING SIGNAL SYSTEM	EACH	1			1	
X0323868	DRAINAGE RESTRICTOR	EACH	1		1		
X0712400	TEMPORARY PAVEMENT	SQ YD	1561		1561		
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	3099		3099		
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	9293		9293		
X4069125	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90, 8"	SQ YD	16321		16321		
XT015000	CHANGEABLE MESSAGE SIGN	CAL MO	100		100		
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4			4	
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	12			12	
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4			4	
XX220000	REMOVE EXISTING LIGHTING SYSTEM	EACH	1			1	
Z0002600	BAR SPLICERS	EACH	142				142
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE, TEST LEVEL 3)	EACH	4				
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE, TEST LEVEL 3)	EACH	2				
Z0022800	FENCE REMOVAL	FOOT	335		335		
Z0076600	TRAINERS	FOUR	1500		1500		
Z0005400	BREAKER RUN CRUSHED STONE	TON	1157				1157
81012600	CONDUIT IN TRENCH 2" DIA. PVC	FOOT	678			678	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MT, 400W	EACH	8			8	
83002400	LIGHT POLE ALUMINUM 40 FT. MH, 15 FT. DAVD ARM	EACH	8			8	
83002350	LIGHT POLE FOUNDATION METAL 11" BOLT CIRCLE 8' 6"	EACH	8			8	
84200100	LIGHTING FOUNDATION REMOVAL	EACH	4			4	
87502310	TRAFFIC SIGNAL POST PAINTED STEEL, 1/4 FT.	EACH	4			4	
88000805	DRAINAGE DEVICE, COLLARING, W/ ALUMINUM SKIRT	EACH	32			32	

*SPECIALTY ITEM

△ SFTY - 3N
 ○ Y080

△ Rev. 7-18-05

Rev.

DRAWN BY
CHECKED BY

M:\98013526\ROADWAY\CONTRACT\GENERAL\ACTION - File\SUMO1-9826C4.dgn