

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	31-1-2, 31B	SALINE	199	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SALINE		
				FOUR LANE	FED 80% STATE 20% TRAFFIC SIGNAL	FED 80% STATE 20% CULVERT SN 083-2014
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	195	195		
20100500	TREE REMOVAL, ACRES	ACRE	0.13	0.13		
20200100	EARTH EXCAVATION	CU YD	6401	6401		
20300100	CHANNEL EXCAVATION	CU YD	1707	1707		
20400100	BORROW EXCAVATION	CU YD	8358	8358		
20700110	POROUS GRANULAR EMBANKMENT	TON	291			291
20800150	TRENCH BACKFILL	CU YD	5448.6	5448.6		
21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	1000	1000		
25000115	SEEDING, CLASS 1B	ACRE	8.1	8.1		
25000350	SEEDING, CLASS 7	ACRE	12.8	12.8		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1484	1484		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	972	972		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	972	972		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	16.2	16.2		
25100115	MULCH, METHOD 2	ACRE	20.9	20.9		
25100630	EROSION CONTROL BLANKET	SQ YD	1478	1478		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	282	282		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3840	3840		
28000300	TEMPORARY DITCH CHECKS	EACH	20	20		
28000500	INLET AND PIPE PROTECTION	EACH	64	64		
28001000	AGGREGATE (EROSION CONTROL)	TON	10.8	10.8		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1416	450		966
28200200	FILTER FABRIC	SQ YD	1416	450		966
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	20,685	20,685		
30201500	LIME	TON	616	616		
35100100	AGGREGATE BASE COURSE, TYPE A	TON	7215	7215		
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	237	237		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3389	3389		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	297	297		
40600895	CONSTRUCTING TEST STRIP	EACH	4	4		
40600990	TEMPORARY RAMP	SQ YD	210	210		
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9/2" (JOINTED)	SQ YD	8157	8157		
42001300	PROTECTIVE COAT	SQ YD	10516	10516		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	139	139		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	3164	3164		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	107	107		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1930	1930		
44000100	PAVEMENT REMOVAL	SQ YD	7640	7640		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8930	8930		
44000300	CURB REMOVAL	FOOT	1001	1001		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3768	3768		
44002805	ISLAND REMOVAL	SQ FT	346	346		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1714	1714		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	635	635		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10524	10524		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2303	2303		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	268	268		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50105220	PIPE CULVERT REMOVAL	FOOT	1161	1161		
50200100	STRUCTURE EXCAVATION	CU YD	685.7			685.7
50800105	REINFORCEMENT BARS	POUND	142,020			142,020
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	720			720
51205200	TEMPORARY SHEET PILING	SQ FT	1261			1261
51500100	NAME PLATES	EACH	1			1
54003000	CONCRETE BOX CULVERTS	CU YD	421			421
54213447	END SECTIONS 12"	EACH	8	8		
54213450	END SECTIONS 15"	EACH	8	8		
54213453	END SECTIONS 18"	EACH	5	5		

*SPECIALTY ITEM

Rev.

DRAWN BY
CHECKED BY

PROJECT NO. / ROADWAY / CONTRACT # / GENERAL / DIVISION / SHEET NO. / DATE