

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	31-1-2, 31B	SALINE	199	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

NEW PAVEMENT, WIDENING & RESURFACING

LOCATION STA. TO STA.	POLY. BIT. CONC. SURF. CSE., SUPER. MIX. "D", N90	BIT. CONC. BINDER CSE., SUPER. IL-19.0, N90	BIT. CONC. BINDER CSE., SUPER. IL-19.0, N90, 8"	P.C.C. PAVT. 9 1/2" (JOINTED)	AGGREGATE BSE. CSE. TYPE A	PROCESSING LIME MOD. SOILS - 12 IN.	BIT. MAT. (PRIME COAT)	STRIP REFLECTIVE CRACK CONTROL TREATMENT	BIT. SURF. REMOVAL-BUTT JOINT	BIT. SURF. REMOVAL (VAR. DEPTH)	TEMPORARY RAMP	MATERIAL TRANSFER DEVICE	PROTECTIVE COAT
	TON	TON	SQ. YD.	SQ. YD.	TON	SQ. YD.	GAL.	FOOT	SQ. YD.	SQ. YDS.	SQ. YD.	TON	SQ. YD.
J.S. RTE. 45													
339+49.68 TO 342+00.00	163	770			153		174	501		1930	41	349	
342+00.00 TO 342+85	50	222			52		53	170				115	
342+85 TO 344+58.20	101	270			106		107	347				234	
344+58.20 TO 374+45	1729	5029	12611			15930	1852	5870				4033	
374+45 TO 375+85	82	235	467			622	87	280				189	
375+85 TO 385+30	547	1773	2311			3150	586	1890				1276	
385+30 TO 391+26				4106	3168								4106
391+26 TO 392+86.47	93	286	391			535	99	321				217	
392+86.47 TO 395+31.47 *	118	372	299		29	448	125	490	135		22	273	
ILL. RTE. 142/STATE ST.													
5+92.63 TO 9+43	81	148	172		277		86	196	80		13	187	
9+43 TO 12+30.63				1535	1227								1535
12+30.63 TO 15+50				1027	861								1027
15+50 TO 15+86.43	13	17	10		23		13					29	
15+86.43 TO 18+15.66	65	171	60		187		69	459	82		14	150	
INTERSECTION @ US RTE 45 & IL 142				1489	1017						120		1489
TOTALS	3042	9293	16321	8157	7100	20685	3251	10524	297	1930	210	7052	8157

\* NOTE: IN AREAS WHERE THE WIDENING IS LESS THAN 3', 12" OF AGGREGATE BASE COURSE TYPE A WILL BE UTILIZED IN LIEU OF PROCESSING LIME MODIFIED SOILS - 12 INCH

NOTE: SEE ENTRANCE SCHEDULE FOR ADDITIONAL PAVING QUANTITIES

DRAWN BY AS  
CHECKED BY DB

1. 1/2" PROPOSED ROADWAY CONTRACT GENERAL  
SCALE: 1"=20' (PLAN)  
DATE: 12/28/07