

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	31-1-2, 31B	SALINE	199	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWERS & END SECTIONS

LOCATION STA. TO STA.	STORM SEWERS, CLASS A, TYPE 2								STORM SEWERS RUBBER GASKET CLASS A, TYPE 2			STORM SEWERS, CLASS B, TYPE 1	P.R.C. FLARED END SECTION	TRENCH BACKFILL
	12 INCH FEET	15 INCH FEET	18 INCH FEET	24 INCH FEET	30 INCH FEET	36 INCH FEET	42 INCH FEET	48 INCH FEET	15 INCH FEET	18 INCH FEET	24 INCH FEET	4 INCH FEET	24 INCH EACH	CU.YD.
U.S. RTE. 45														
STA 340+62.00 LT TO STA 341+97.00 LT		135												9.9
STA 342+03.00 LT TO STA 343+17.00 LT		114												13.8
STA 343+23.00 LT TO STA 343+96.00 LT				73										8.8
STA 344+02.00 LT TO STA 344+80.00 LT											78			9.0
STA 344+86.00 LT TO STA 345+63.00 LT											77			8.9
STA 345+69.00 LT TO STA 348+18.00 LT					249									39.3
STA 348+24.00 LT TO STA 349+25.00 LT					101									19.4
STA 349+31.00 LT TO STA 350+97.00 LT					166									20.6
STA 351+03.00 LT TO STA 352+07.00 LT					104									16.4
STA 352+11.00 LT TO STA 352+27.00 LT					16									3.1
STA 352+20.00 LT	9													
STA 352+33.00 LT TO STA 353+47.00 LT					114									29.6
STA 353+50.00 LT		3												
STA 353+53.00 LT TO STA 354+97.00 LT						144								89.1
STA 355+00.00 LT		10												
STA 355+03.00 LT TO STA 356+47.00 LT						144								103.4
STA 356+53.00 LT TO STA 357+17.00 LT						64								49.1
STA 357+23.00 LT TO STA 357+97.00 LT						74								60.4
STA 358+03.00 LT TO STA 358+97.00 LT						94								86.0
STA 359+03.00 LT TO STA 359+97.00 LT						94								95.3
STA 360+00.00 LT			17											
STA 360+03.00 LT TO STA 360+97.00 LT							94							102.5
STA 361+03.00 LT TO STA 361+97.00 LT							94							107.8
STA 362+03.00 LT TO STA 362+97.00 LT							94							112.8
STA 363+03.00 LT TO STA 364+37.00 LT								134						172.1
STA 364+40.00 LT			13											
STA 364+43.00 LT TO STA 365+77.00 LT								134						195.4
STA 365+83.00 LT TO STA 366+00.00 LT								17						26.8
STA 366+43.00 LT TO STA 368+82.00 LT				239										202.2
STA 368+88.00 LT TO STA 369+97.00 LT				109										83.3
STA 370+03.00 LT TO STA 371+06.00 LT				103										42.4
STA 371+12.00 LT TO STA 371+77.00 LT				65										21.0
STA 371+83.00 LT TO STA 372+70.00 LT				87										25.6
STA 372+76.00 LT TO STA 374+27.00 LT				151										39.9
STA 374+30.00 LT	7													
STA 374+33 LT TO STA 375+67.00 LT										134				31.5
STA 375+33.00 LT TO STA 375+49.00 LT	16													
STA 375+51.00 LT TO STA 375+67.00	21													
STA 375+73.00 LT TO STA 376+50.00 LT				77										15.8
STA 376+53.00 LT	6													
STA 376+56.00 LT TO STA 377+33.00 LT				77										15.8
STA 377+36.00 LT	6													
STA 377+39.00 LT TO STA 378+42.00 LT				103										27.2
STA 378+60.00 LT	13													
STA 378+48.00 LT TO STA 380+05.00 LT				157										46.2
STA 380+23.00 LT	13													17.2
STA 380+11.00 LT TO STA 381+17.00 LT				106										28.0
STA 381+20.00 LT	6													
STA 381+23.00 LT TO STA 382+21.00 LT				98										23.0
STA 382+24.00 LT	6													
STA 382+27.00 LT TO STA 382+65.00 LT				38										7.8
STA 382+67.00 LT	4													0.5
STA 382+69.00 LT TO STA 383+34.00 LT				65										13.3
STA 382+70 to STA 382+89.00 LT											19			
STA 383+37.00 LT	6													
STA 383+40.00 LT TO STA 385+22.00 LT				182										42.8
STA 385+25.00 LT	4													
STA 385+28.00 LT TO STA 386+39.00 LT				111										35.9
STA 386+42.00	6													
STA 386+45.00 LT TO STA 387+16.00 LT				71										22.9
STA 387+22.00 LT TO STA 387+74.00 LT										62				14.6
STA 388+63.24 LT TO STA 389+92.00 LT				129										15.0
STA 389+00.00 LT	6													
STA 389+98.00 LT TO STA 390+97.00 LT				99										11.5
STA 391+00.00 LT	3													
STA 391+03.00 LT TO STA 392+17.00 LT				114										16.6
STA 392+00.00 LT	4													
STA 392+23.00 LT TO STA 392+87.00 LT				64										11.2
STA 392+90.00 LT	5													
STA 392+93.00 LT TO STA 394+00.00 LT				107										15.6
STA 394+03.00 LT	5													
STA 394+06.00 LT TO STA 395+28.00 LT				122										17.8
SUBTOTALS	146	262	30	2547	750	614	282	285	0	0	351	19	0	2224.0

DRAWN BY: J.S.
 CHECKED BY: J.B.

V. M. / PROJ. 332.6 / ROADWAY / CONTRACT # 4 / GENERAL
 3/23/06
 321001-35864-GP
 3/23/06 321001-35864-GP