

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	31-1-2, 31B	SALINE	199	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PIPE CULVERTS AND END SECTIONS

LOCATION	PIPE CULVERTS - CLASS D			END SECTION			TRENCH BACKFILL CU. YD.
	TYPE 2 12" FOOT	TYPE 2 15" FOOT	TYPE 2 18" FOOT	12" EACH	15" EACH	18" EACH	
	U.S. RTE. 45						
STA 345+31 RT		11			1		
STA 347+01 RT		30			2		4.3
STA 358+00 RT			15			1	
STA 361+00 RT		18			1	1	
STA 366+67 RT		28			2		7.9
STA 372+80 RT	16			1			
STA 340+62 LT	6			1			
STA 342+00 LT	6			1			
STA 343+20 LT	4			1			
STA 344+83 LT			8			1	
STA 345+66 LT			7			1	
STA 349+28 LT			7			1	
STA 351+00 LT			8			1	
STA 370+00 LT	18			1			
STA 371+80 LT	15			1			
STA 372+73 LT	12			1			
ILL. RTE. 142							
STA 7+62 RT		34			2		4.9
STA 10+00 RT	7			1			
TOTALS	84	121	45	8	8	5	17.1

NOTE: SEE STORM SEWERS AND END SECTIONS SCHEDULE FOR ADDITIONAL END SECTIONS AND TRENCH BACKFILL.

PIPE CULVERT REMOVAL

LOCATION	OFFSET		PIPE CULVERT REMOVAL FOOT
	LEFT FEET	RIGHT FEET	
U.S. RTE. 45			
340+92.00		26	38
343+12.00		25	52
343+73.00	40		68
345+24.00	23		40
347+14.00		25	26
347+70.00		24	65
347+88.00	23		49
348+87.00		24	49
349+78.00	23		33
351+60.00		23	43
351+65.00	23		91
354+09.00	23		49
354+31.00		27	66
354+74.00	26		38
355+92.00		27	72
358+63.00		32	55
364+78.00	44		43
366+66.00		53	30
369+51.00	49		59
370+77.00	47		49
372+22.00	47		41
393+36.00		35	9
393+54.00		36	36
394+00.00		39	21
ILL. RTE. 142/STATE ST.			
7+62.00		35	39
TOTALS			1161

EROSION CONTROL

LOCATION STA. TO STA.	TEMPORARY DITCH CHECK	INLET AND PIPE PROTECTION
	EACH	
U.S. RTE. 45		
334+00 TO 340+00	2	1
340+00 TO 346+00	2	7
346+00 TO 352+00	1	5
352+00 TO 358+00	2	6
358+00 TO 364+00	3	2
364+00 TO 370+00	6	3
370+00 TO 376+00	3	6
376+00 TO 382+00		9
382+00 TO 386+00		6
386+00 TO 392+00		4
392+00 TO 396+89.14		6
ILL. RTE. 142		
6+50 TO 12+50	1	6
12+50 TO 18+50		3
TOTALS	20	64

SEE ALSO SEDIMENT BASIN DETAIL (SHEET 120) FOR AGGREGATE (EROSION CONTROL) AND EARTH EXCAVATION FOR EROSION CONTROL.

SEEDING

LOCATION STA. TO STA.	SEEDING CLASS 1B	EROSION CONTROL BLANKET	SEEDING CLASS 7	TEMPORARY EROSION CONTROL SEEDING	MULCH METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE
	ACRE	SQ. YD.	ACRE	POUND	ACRE	POUND	POUND	POUND	TON
U.S. RTE. 45									
334+00 TO 340+00	0.3	44	0.5	150	0.8	56	36	36	0.6
340+00 TO 346+00	0.7	133	1.1	330	1.8	128	84	84	1.4
346+00 TO 352+00	0.6	133	1.2	360	1.8	120	72	72	1.2
352+00 TO 358+00	0.7	133	1.3	390	2.0	136	84	84	1.4
358+00 TO 364+00	0.9	133	1.5	450	2.4	168	108	108	1.8
364+00 TO 370+00	0.9	111	1.3	390	2.2	160	108	108	1.8
370+00 TO 376+00	1.0	142	1.5	450	2.5	180	120	120	2
376+00 TO 382+00	0.7	105	1.1	330	1.8	128	84	84	1.4
382+00 TO 386+00	0.5	92	0.7	210	1.2	88	60	60	1
386+00 TO 392+00	0.7	101	1.1	330	1.8	128	84	84	1.4
392+00 TO 396+89.14	0.3	85	0.5	150	0.8	56	36	36	0.6
RTE 142									
6+50 TO 12+50	0.5	133	0.6	180	1.1	84	60	60	1
12+50 TO 18+50	0.3	133	0.4	120	0.7	52	36	36	0.6
TOTALS	8.1	1478	12.8	3840	20.9	1484	972	972	16.2

STORM SEWER REMOVAL

LOCATION	OFFSET		STORM SEWER REMOVAL 12" FOOT	STORM SEWER REMOVAL 24" FOOT
	LEFT FEET	RIGHT FEET		
U.S. RTE. 45				
372+82 LT TO 374+35 LT	48		153	
374+35 LT TO 375+06 LT	42		71	
375+06 LT TO 375+88 LT	32		82	
375+37 RT TO 375+87 RT		35		50
ILL. RTE. 142				
6+68 LT TO 12+40 LT	28			572
14+95 LT TO 18+05 LT	28		310	
12+81 RT TO 14+00 RT			119	
TOTALS			735	622

DRAWN BY  
CHECKED BY

M:\PROJECTS\ROADWAY\CONTRACT GENERAL  
DATE: 10/10/01  
BY: [Signature]