

SUMMARY OF QUANTITIES								
ITEM NO.	DESCRIPTION	UNIT	AS BID QUANTITIES			AS BUILT QUANTITIES		
			TOTAL QUANTITY	95% FEDERAL 2.5% STATE 2.5% LOCAL QUANTITY	95% FEDERAL 5% LOCAL QUANTITY	TOTAL QUANTITY	95% FEDERAL 2.5% STATE 2.5% LOCAL QUANTITY	95% FEDERAL 5% LOCAL QUANTITY
AR152410	UNCLASSIFIED EXCAVATION	CU. YD.	796	796				
AR152442	OFFSITE BORROW EXCAVATION	CU. YD.	3,487	3,487				
AR152531	EXPLORATION TRENCH	LIN. FT.	20	20				
AR152532	FIELD TILE REPAIR	LIN. FT.	20	20				
AR156510	SILT FENCE	LIN. FT.	130	130				
AR156512	BALES	EACH	15	15				
AR161510	CLASS C FENCE	LIN. FT.	173	173				
AR161900	REMOVE CLASS C FENCE	LIN. FT.	190	190				
AR162504	CLASS E FENCE 4'	LIN. FT.	37	37				
AR162900	REMOVE CLASS E FENCE	LIN. FT.	20	20				
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	1,864	719	1,145			
AR401610	BITUMINOUS SURFACE COURSE	TON	620	239	381			
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SQ. YD.	21	21				
AR501200	PCC T-HANGAR FLOOR - COMPLETE	SQ. YD.	1,509		1,509			
AR501910	REMOVE & REPLACE PCC PAVEMENT	SQ. YD.	14	14				
AR602510	BITUMINOUS PRIME COAT	GAL.	1,273	491	782			
AR603510	BITUMINOUS TACK COAT	GAL.	180	69	111			
AR701512	12" RCP, CLASS IV	LIN. FT.	118	118				
AR701515	15" RCP, CLASS IV	LIN. FT.	154	154				
AR701518	18" RCP, CLASS IV	LIN. FT.	66	66				
AR701524	24" RCP, CLASS IV	LIN. FT.	106	106				
AR701536	36" RCP, CLASS IV	LIN. FT.	442	442				
AR701900	REMOVE PIPE	LIN. FT.	66	66				
AR751411	INLET TYPE A	EACH	2	2				
AR751412	INLET TYPE B	EACH	1	1				
AR751540	MANHOLE 4'	EACH	1	1				
AR751550	MANHOLE 5'	EACH	2	2				
AR751570	MANHOLE - SPECIAL	EACH	1	1				
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	1	1				
AR901510	SEEDING	ACRE	1.3	1.3				
AR908510	MULCHING	ACRE	1.3	1.3				

INDEX TO SHEETS	
NO.	DESCRIPTION
1	COVER SHEET
2	IMPROVEMENT AND SAFETY PLAN
3	INDEX TO SHEETS AND SUMMARY OF QUANTITIES
4	TYPICAL SECTION AND FUNDING LAYOUT
5	T-HANGAR FLOOR DETAILS
6	T-HANGAR PAVEMENT AND GRADING LAYOUT
7	STORM SEWER LAYOUT
8	STORM SEWER SPECIAL DETAILS
9	EROSION CONTROL PLAN
10-13	T-HANGAR AREA CROSS SECTIONS
14-17	STANDARD DRAWINGS

JACKSONVILLE MUNICIPAL AIRPORT JACKSONVILLE, ILLINOIS	
INDEX TO SHEETS AND SUMMARY OF QUANTITIES	
HUTCHISON ENGINEERING, INC. JACKSONVILLE, ILLINOIS	
DRAWN BY: T.J.D. DATE: JUNE, 2005	ILL. PROJ. NO. IJX-3435 AIP PROJ. NO. 3-17-0054-B10