

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY LIGHTING				
				80% FED 20% STATE I000	80% FED 20% STATE Y030-1E	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,508	1,508					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	323	323					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	762	762					
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	9,956	9,956					
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	4,620	4,620					
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1,234	1,234					
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	145	145					
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	86	86					
* 78005120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	480	480					
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	116	116					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	9,754	9,754					
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	3,950	3,950					
* 78008340	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	2,145	2,145					
* 78008350	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	693	693					
* 78008370	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	128	128					
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	156	156					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	9	9					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	24	24					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	12,625	12,625					
* 81100220	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., PVC COATED GALVANIZED STEEL	FOOT	2,008						2,008
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	5,629						5,629
* 81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	268						268
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,084						1,084
* 81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,293						1,293
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	2,591						2,591
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	9		9				
* 84400125	RELOCATE EXISTING TEMPORARY LIGHTING UNIT	EACH	9		9				
* 87000150	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 6 AND NO. 8 GROUND	FOOT	1,793						1,793
* 87000200	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 8 AND NO. 10 GROUND	FOOT	4,145						4,145
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2	2					
* 88030012	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED	EACH	4	4					
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	4					
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	4	4					

* SPECIALTY ITEMS

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL, 60606

USER NAME = #USER#
FILE NAME = #FILENAME#
PLOT SCALE = #SCALE#
PLOT DATE = 5/7/2009

DESIGNED - DM
DRAWN - MS
CHECKED - DS
DATE - 5/08/09

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 6 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
389	2424-2B-R	COOK	398	6
CONTRACT NO. 60D61				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				