

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY LIGHTING	80% FED	80% FED	80% FED	80% FED
				80% FED 20% STATE 1000	80% FED 20% STATE Y030-1E	20% STATE	20% STATE	20% STATE	
X0326607	GALVANIZED STEEL SLEEVE 3", <i>INCLUDING</i> CORING, PATCH, FIREPROOFING	EACH	12						12
X0326608	GALVANIZED STEEL SLEEVE 3-1/2", <i>INCLUDING</i> CORING, PATCH, FIREPROOFING	EACH	8						8
81100420	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., PVC COATED GALVANIZED STEEL	FOOT	62						62
X0326597	ELECTRICAL DEMOLITION	L SUM	1						1
X0326598	ELECTRICAL EQUIPMENT AND CONDUIT DISPOSAL, NOT INCLUDING HAZARDOUS MATERIALS	L SUM	1						1
X0326599	TRANSFORMER 480-208/120V, 45 KVA	EACH	2						2
X0326600	TRANSFORMER 480-208/120V, 15 KVA	EACH	3						3
X0326601	DISCONNECT SWITCH 3-POLE, 600V, 30AMP	EACH	28						28
X0326602	DISCONNECT SWITCH 3-POLE, 600V, 100AMP	EACH	2						2
X0326603	DISCONNECT SWITCH 3-POLE, 600V, 200AMP	EACH	6						6
X0326604	DISCONNECT SWITCH 3-POLE, 600V, 400AMP	EACH	2						2
X0326609	GROUNDING	L SUM	1						1
X0326610	ELECTRICAL TERMINATION 600V	EACH	456						456
X0326611	ELECTRICAL CONDUIT AND CABLE TAGS	EACH	208						208
X0326612	MOGUL FITTING 1"-DIAMETER	EACH	12						12
X0326613	MOGUL FITTING 2-1/2"-DIAMETER	EACH	1						1
X0326564	VECTOR-CONTROLLED MOTOR DRIVES	EACH	8						8
X0326633	NEMA 4X STAINLESS STEEL ENCLOSURE FOR 75HP VECTOR-CONTROLLED MOTOR DRIVES	EACH	8						8
X0326615	INTEGRATED BRIDGE CONTROL SYSTEM	L SUM	1						1
X0326552	BASCULE SPAN LIGHTS RED/GREEN	EACH	4						4
X0326553	PIER LIGHTS	EACH	8						8
X0326554	MOTOR SPEED SWITCHES	EACH	8						8
X0326555	MAIN SPAN DRIVE MOTORS	EACH	8						8
X0326634	PVC COATED 3/4" GALVANIZED STEEL CONDUIT	FOOT	5,000						5,000
X0326619	#12 AWG XHHW-2 WIRE	FOOT	8,500						8,500
X0326620	#10 AWG XHHW-2 WIRE	FOOT	1,500						1,500
X0326621	TYPE 'A' INTERIOR HID METAL HALIDE LUMINAIRE	EACH	40						40
X0326622	TYPE 'B' INTERIOR INDUSTRIAL FLUORESCENT LUMINAIRE	EACH	27						27
X0326623	TYPE 'B-1' INTERIOR INDUSTRIAL FLUORESCENT LUMINAIRE W/LOW TEMPERATURE BALLAST	EACH	26						26
X0326624	TYPE 'C' RECESSED FLUORESCENT LUMINAIRE 2'x2'	EACH	10						10
X0326625	TYPE 'D' PENDANT OR SURFACE MOUNTED FLUORESCENT	EACH	12						12
X0326626	TYPE 'E' LED EXIT SIGN W/BATTERY PACK WALL MOUNTED	EACH	18.00						18.00
X0326627	TYPE 'E-1' LED EXIT SIGN W/BATTERY PACK CEILING MOUNTED	EACH	2						2
X0326628	TYPE 'F' STAIR FLUORESCENT LUMINAIRE	EACH	8						8
X0326629	TYPE 'G' EMERGENCY LIGHT BATTERY UNIT WALL MOUNTED	EACH	50						50
X0326630	TYPE 'G-1' EMERGENCY LIGHT BATTERY UNIT CEILING MOUNTED	EACH	2.0						2.0
X0326631	TYPE 'H' OUTDOOR STAIR HID METAL HALIDE WALL PACK LUMINAIRE WITH PHOTO CELL CONTROL	EACH	2.0						2.0
X0326632	WEATHER PROOF TOGGLE SWITCH 20AMP	EACH	24						24

*Specialty Items

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606

USER NAME = #USER#
FILE NAME = #FILENAME#
PLOT SCALE = #SCALE#
PLOT DATE = 5/7/2009

DESIGNED - DM
DRAWN - MS
CHECKED - DS
DATE - 5/08/09

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
SUMMARY OF QUANTITIES

SCALE: SHEET NO.10 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RTE. 389	SECTION 2424-2B-R	COUNTY COOK	TOTAL SHEETS 398	SHEET NO. 10
CONTRACT NO. 60D61			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	