

CHAIN LINK FENCE, 8'						
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT	
Wacker Dr.	100+63.53	28.4' RT	101+14.53	28.4' RT	51	
	100+63.93	65.0' RT	100+63.53	28.4' RT	37	
	100+63.93	65.0' RT	100+79.94	65.0' RT	16	
	100+79.94	65.0' RT	100+79.93	54.0' RT	12	
	100+79.93	54.0' RT	101+15.43	54.0' RT	36	
	101+14.53	28.4' RT	101+14.53	40.4' RT	12	
	101+14.43	56.4' RT	102+32.51	55.9' RT	118	
	101+14.93	36.4' RT	101+39.45	36.4' RT	25	
	101+82.63	36.3' RT	102+32.29	35.9' RT	50	
	102+32.29	35.9' RT	102+32.51	55.9' RT	20	
	TOTAL					380

TEMPORARY CONCRETE BARRIER					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
STAGE I					
	365+53.07	1.6' RT	379+39.55	29.4' LT	1,386
	381+66.32	29.1' LT	385+25.77	6.4' RT	359
	371+58.74	9.0' RT	372+40.61	1.1' RT	82
	377+80.00	14.6' RT	378+50.00	13.7' RT	70
	379+22.46	1.67' LT	379+39.22	3.05' LT	16
	381+65.66	1.06' LT	381+78.21	2.07' LT	12
STAGE II					
	372+40.61	21.3' RT	379+71.57	18.4' RT	731
	381+98.34	18.6' RT	385+97.25	5.4' RT	399
	379+58.30	1.25' RT	379+70.70	0.26' RT	12
	381+97.29	2.23' RT	382+13.85	0.86' RT	16
TOTAL:					3,084

RELOCATE TEMPORARY CONCRETE BARRIER					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
WINTER LANE CONFIGURATION					
	365+53.07	1.3' RT	372+40.61	2.8' RT	688
STAGE II					
	365+53.07	1.3' RT	372+40.61	21.3' RT	688
TOTAL:					1,375

CONCRETE BARRIER REMOVAL (SPECIAL)					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
Congress Prkwy	365+53.07	3.2 RT'	372+40.61	2.8 RT'	688
	377+01.00	CL	377+50.23	CL	49
TOTAL:					737

CONCRETE MEDIAN REMOVAL							
LOCATION	FROM STATION	WIDTH	OFFSET	TO STATION	WIDTH	OFFSET	SO FT
Congress Prkwy	377+67.98	4.75	CL	378+46.48	4.75	CL	373
	383+45.62	4.75	CL	385+72.62	4.75	CL	1,078
TOTAL:							1,451

CHANGEABLE MESSAGE SIGN		
LOCATION	CAL MO	
I-290 EASTBOUND:		
EB I-290 AT WEST OF HOMAN AVE.	14	
EB I-290 AT EAST OF ASHLAND AVE.	14	
I-90/94 WESTBOUND:		
EB I-90/94 AT SOUTH OF CHICAGO AVE.	14	
EB I-90/94 AT NORTH OF MADISON ST.	14	
I-90/94 WESTBOUND:		
WB I-90/94 AT SOUTH OF 35TH ST.	14	
I-55 NORTHBOUND:		
NB I-55 AT EAST OF ASHLAND AVE.	14	
CONGRESS PKWY ALTERNATIVE ROUTES - INBOUND:		
END OF EB SACRAMENTO BLVD. EXIT RAMP	14	
SB SACRAMENTO BLVD. AT FILLMORE ST.	14	
EB ROOSEVELT RD. AT MORGAN ST.	14	
NB SACRAMENTO BLVD. AT JACKSON BLVD.	14	
EB WASHINGTON BLVD. AT 150' EAST OF JEFFERSON ST.	14	
NB LAKE SHORE DR. AT ROOSEVELT RD.	14	
CONGRESS PKWY ALTERNATIVE ROUTES - OUTBOUND:		
WB ROOSEVELT RD. AT JEFFERSON BLVD.	14	
WB ROOSEVELT RD. AT 100' WEST OF CALIFORNIA AVE.	14	
WB ADAMS ST. AT ASHLAND AVE.	14	
VARIOUS LOCATIONS AS DIRECTED BY THE ENGINEER		
	70	
TOTAL:		280

TEMPORARY CONCRETE BARRIER REMOVAL					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
Congress Prkw	377+76.20	51.9' LT	378+84.95	57.9' LT	109
STAGE I					
	372+40.61	28.8' LT	379+39.55	29.4' LT	699
	381+66.32	29.1' LT	385+25.77	6.4' RT	359
	371+58.74	9.0' RT	372+40.61	1.1' RT	82
	377+80.00	14.6' RT	378+50.00	13.7' RT	70
STAGE II					
	365+53.07	1.3' RT	379+71.57	18.4' RT	1,419
	381+98.34	18.6' RT	385+97.25	5.4' RT	399
TOTAL:					3,136

TEMPORARY THRIE BEAM STEEL PLATE GUARDRAIL, TYPE D (SPECIAL)					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
STAGE I					
	379+39.55	29.7' LT	381+66.32	29.7' LT	227
STAGE II					
	379+71.57	18.9' RT	381+98.34	18.6' RT	227
TOTAL:					454

TEMPORARY THRIE BEAM STEEL PLATE GUARDRAIL, TYPE D REMOVAL (SPECIAL)					
LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
STAGE I					
	379+39.55	29.7' LT	381+66.32	29.7' LT	227
STAGE II					
	379+71.57	18.9' RT	381+98.34	18.6' RT	227
TOTAL:					454

PB Americas, Inc.
 230 WEST MONROE STREET,
 SUITE 900
 CHICAGO, IL. 60606

USER NAME = #USER#	DESIGNED - DM	REVISED -
FILE NAME = #FILENAME#	DRAWN - MS	REVISED -
PLOT SCALE = #SCALE#	CHECKED - DS	REVISED -
PLOT DATE = 9/7/2009	DATE - 5/08/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
 SCHEDULE OF QUANTITIES

SCALE= NONE	SHEET NO. 18 OF 83 SHEETS	STA. 377+01.00 TO STA. 382+45.28
-------------	---------------------------	----------------------------------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
389	2424-2B-R	COOK	398	18
CONTRACT NO. 60D61				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				