

GENERAL NOTES

This work shall be done in accordance with Section 704 of the Standard Specifications. Temporary Concrete Barrier will be measured in feet along the centerline of the barrier and shall include the cost of renting/owning the barrier for the time required on the job plus hauling to and from the project site, as well as one placement and removal from the roadway in accordance with Section 704 of the Standard Specification. This shall be paid for at the contract unit price per Foot for TEMPORARY CONCRETE BARRIER.

Relocate Temporary Concrete Barrier will be paid for in Feet along the centerline of the barrier, and will be paid for each time the barrier is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Foot for RELOCATE TEMPORARY CONCRETE BARRIER.

COMMITMENTS:

1. Two Trees – one at approximately Lt. Sta. 919+10 and one at approximately Lt. Sta. 919+70 shall be saved during construction. These trees shall be marked "To Be Saved" on the contract plan sheets.
2. Access to the park shall be kept open at all times.
3. No construction activities shall take place beyond construction limits in the park. This includes driving and parking vehicles and equipment and stockpiling materials.

FILE NAME = 64F19.GN.DOCX	USER NAME =	DESIGNED - Engineering Systems	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	ROUTE	SECTION	COUNTY	LEGAL PROJECTS	SHEET NO.
	PLOT SCALE =	DRAWN -	REVISED -			FAP 22	15BR-1	Whiteside	146	5
PLOT DATE = 6/12/2014 3:23 PM	CHECKED -	REVISED -	(IL 78)		CONTRACT NO. 64F19					
DATE = 1/23/2014 10:34 AM	DATE	REVISED -	SCALE		SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS