

SUMMARY OF QUANTITIES

07POL 07POL 07C 02

CODE NUMBER		UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% STATE		20% CITY OF MORRISON
				ROADWAY 0004 URBAN	SN 098-0118 0011 URBAN	ROADWAY 0028 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	74	74	0	0
20200100	EARTH EXCAVATION	CU YD	3,190	3,190	0	0
25000100	SEEDING, CLASS 1	ACRE	1.5	1.5	0	0
25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75	0	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	175	175	0	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	175	175	0	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	175	175	0	0
25000750	MOWING	ACRE	2	2	0	0
25100630	EROSION CONTROL BLANKET	SQ YD	9,254	9,254	0	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,167	1,167	0	0
28000305	TEMPORARY DITCH CHECKS	FOOT	251	251	0	0
28000400	PERIMETER EROSION BARRIER	FOOT	1,454	1,454	0	0
28000500	INLET AND PIPE PROTECTION	EACH	6	6	0	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	20	20	0	0
28100109	STONE RIPRAP, CLASS A5	SQ YD	410	0	410	0
28200200	FILTER FABRIC	SQ YD	430	20	410	0
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	3,710	3,660	0	50
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,390	1,112	0	278
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	541	541	0	0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	559	559	0	0
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0	0
40600990	TEMPORARY RAMP	SQ YD	93	93	0	0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	376	376	0	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	606	606	0	0
40603415	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, N50	TON	145	116	0	29
40800050	INCIDENTIAL HOT-MIX ASPHALT SURFACING	TON	54	54	0	0
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	71	71	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	242	194	0	48
42400800	DETECTABLE WARNINGS	SQ FT	40	32	0	8
44000100	PAVEMENT REMOVAL	SQ YD	113	113	0	0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3,068	3,068	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	68	68	0	0
44000600	SIDEWALK REMOVAL	SQ FT	26	21	0	5
44004250	PAVED SHOULDER REMOVAL	SQ YD	59	59	0	0

34

* SPECIALITY ITEM

†100% CITY OF MORRISON (07POL)

FILE NAME *	USER NAME = Fossilermj	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\p_w\k\p\idat\fosserm\ad\14994\02	ht-schedule.dgn	DRAWN - _____	REVISED - _____			22	150R-1	WHITESIDE	146	6	
	PLOT SCALE = 1/8" = 1'	CHECKED - _____	REVISED - _____			CONTRACT NO. 64F19					
Default	PLOT DATE = Fri Jun 12 10:01:08 2014	DATE - _____	REVISED - _____			[ILLINOIS] FED. AID PROJECT					

Rev.