

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% STATE		20% CITY OF MORRISON
				ROADWAY 0004 URBAN	SN 098-0118 0011 URBAN	ROADWAY 0028 URBAN
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	2,479	2,436	0	43
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	37	37	0	0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1	0
50200100	STRUCTURE EXCAVATION	CU YD	235	0	235	0
50200300	COFFERDAM EXCAVATION	CU YD	180	0	180	0
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1	0	1	0
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1	0	1	0
50300225	CONCRETE STRUCTURES	CU YD	186.8	0	186.8	0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	462.8	0	462.8	0
50300260	BRIDGE DECK GROOVING	SQ YD	660	0	660	0
50300280	CONCRETE ENCASEMENT	CU YD	9.8	0	9.8	0
50300300	PROTECTIVE COAT	SQ YD	1,050	0	1,050	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	125,200	0	125,200	0
50800515	BAR SPLICERS	EACH	456	0	456	0
50901720	BICYCLE RAILING	FOOT	191	28	156	7
50901750	PARAPET RAILING	FOOT	152	0	152	0
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1,286	0	1,286	0
51202305	DRIVING PILES	FOOT	1,286	0	1,286	0
51203200	TEST PILE METAL SHELLS	EACH	4	0	4	0
51500100	NAME PLATES	EACH	1	0	1	0
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	0	0
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	116	116	0	0
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	121	121	0	0
542D5476	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 21"	FOOT	207	207	0	0
542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	53	53	0	0
542D5485	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	40	40	0	0
54213447	END SECTIONS 12"	EACH	2	2	0	0
54214296	END SECTIONS, EQUIVALENT ROUND-SIZE 21"	EACH	4	4	0	0
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"	EACH	1	1	0	0
54215410	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 10"	EACH	1	1	0	0
54215412	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 12"	EACH	1	1	0	0
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2	2	0	0
54260311	TRAVERSABLE PIPE GRATE	FOOT	181	181	0	0
54261615	CONCRETE END SECTION, STANDARD 542001, 15", 1:6	EACH	1	1	0	0

\* SPECIALITY ITEM    Δ NP 100% STATE    † 100% CITY OF MORRISON

FILE NAME *	USER NAME * Faslermj	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pvidot\Faslermj\02149594\02\pht-schedule.dgn	PLOT SCALE * 40.0000 1/4 in.	DRAWN - _____	REVISED - _____			22	15BR-1	WHITESIDE	146	7
Default	PLOT DATE * Fri Jun 13 10:02:01 2014	CHECKED - _____	REVISED - _____			SCALE: _____ SHEET _____ OF _____ SHEETS   STA. _____ TO STA. _____				
[ILLINOIS] FED. AID PROJECT										