

SUMMARY OF QUANTITIES

CONSTRUCTION CODE		
100% STATE		20% CITY OF MORRISON
ROADWAY 0004 URBAN	SN 098-0118 0011 URBAN	ROADWAY 0028 URBAN

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	100% STATE ROADWAY 0004 URBAN	SN 098-0118 0011 URBAN	20% CITY OF MORRISON ROADWAY 0028 URBAN
54263618	CONCRETE END SECTION, STANDARD 542011, 18", 1:6	EACH	2	2	0	0
54263624	CONCRETE END SECTION, STANDARD 542011, 24", 1:6	EACH	2	2	0	0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	62	0	62	0
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2	0	0
60100080	FRENCH DRAINS	CU YD	3	3	0	0
60100925	PIPE DRAINS 8"	FOOT	20	20	0	0
60100935	PIPE DRAINS 10"	FOOT	20	20	0	0
60100945	PIPE DRAINS 12"	FOOT	82	82	0	0
60107600	PIPE UNDERDRAINS 4"	FOOT	1,934	1,934	0	0
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	55	55	0	0
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0	0
† 60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	0	0	1
60608562	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4, 12	FOOT	28	28	0	0
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	0	0
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2	2	0	0
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	20	20	0	0
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	1	1	0	0
• 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125	0	0
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	0	0
• 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	2	2	0	0
• 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	2	2	0	0
63200310	GUARDRAIL REMOVAL	FOOT	675	675	0	0
63500105	DELINEATORS	EACH	21	21	0	0
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	14	14	0	0
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	0	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	0	0
67100100	MOBILIZATION	L SUM	1	1	0	0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	0	0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0	0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	0	0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	0	0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	0	0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0	0
70106700	TEMPORARY RUMBLE STRIPS	EACH	3	3	0	0

• SPECIALITY ITEM △ NP 100% STATE † 100% CITY OF MORRISON

FILE NAME =	USER NAME = Fosslermj	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\p\work\p\dot\Fosslermj\08149594\02	hnt-schedule.dgn	DRAWN - _____	REVISED - _____			22	150R-1	WHITESIDE	146	8	
Default	PLOT SCALE = 1/8" = 1' / in.	CHECKED - _____	REVISED - _____			SCALE: _____ SHEET _____ OF _____ SHEETS		STA. _____ TO STA. _____		CONTRACT NO. 64F19	
	PLOT DATE = Fri Jun 13 10:02:20 2014	DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT					