

# SCHEDULE OF QUANTITIES

**60100935 PIPE DRAINS 10"**

FOOT	LOCATION
20	Contingency for Field Tile
20	TOTAL

**60100945 PIPE DRAINS 12"**

FOOT	LOCATION	COMMENTS
	IL ROUTE 78	
29	Rt. Sta. 909 + 19.97	Outlet for "TYPE E INLET BOX"
33	Lt. Sta. 909 + 19.97	Outlet for "TYPE E INLET BOX"
20	Contingency for Field Tile	
82	TOTAL	

**60107600 PIPE UNDERDRAINS 4"**

FOOT	LOCATION	COMMENTS
	IL ROUTE 78	
269.6	Lt. Sta. 906 + 59.94 - 909 + 12.49	IL 78 Mainline ( Cost Included to Tie into pipe culvert Sta. 99+46.02)
253.3	Rt. Sta. 906 + 82.09 - 909 + 12.49	IL 78 Mainline (Cost Included to Tie into pipe culvert Sta. 100+55.77)
640.1	Lt. Sta. 910 + 94.21 - 917 + 34.28	IL 78 Mainline
678.0	Rt. Sta. 911 + 01.96 - 917 + 80.00	IL 78 Mainline
1,841.0	SUB-TOTAL (IL ROUTE 78)	
	FRENCH CREEK ROAD	
93.0	Lt. Sta. 100 + 63.62 - 101 + 55.56	FCR (Cost Included for Slope to Tie into pipe culvert Sta. 100+63.62)
93.0	SUB-TOTAL (FRENCH CREEK ROAD)	
1,934	TOTAL	

**60108100 PIPE UNDERDRAINS 4" (SPECIAL)**

FOOT	LOCATION	COMMENTS
	IL ROUTE 78	
20	Rt. Sta. 913 + 75.00	IL 78 Mainline, Slope 2%
35	Lt. Sta. 913 + 75.00	IL 78 Mainline, Slope 1%
55	TOTAL	

**60218400 MANHOLES TYPE A 4'-DIAMETER TYPE 1 FRAME CLOSED LID**

EACH	LOCATION	COMMENTS
	IL ROUTE 78	
1	Rt. Sta. 917 + 75	24.81' o/s; Lid to have the word "STORM" written
1	TOTAL	

**60255800 MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME CLOSED LID**

EACH	LOCATION	COMMENTS
	IL ROUTE 78	
1	Sta. 913 + 70	Existing Sanitary Sewer; Lid to have the word "SANITARY" written
1	TOTAL	

**60608562 COMBINATION CONCRETE CURB AND GUTTER TYPE M-4.12**

FOOT	LOCATION
	MIT ENTRANCE
9.8	Rt. Sta. 99 + 02.24 - 99 + 12
17.8	Lt. Sta. 99 + 02.24 - 99 + 20
28	TOTAL

**60900515 CONCRETE THRUST BLOCKS**

EACH	LOCATION	COMMENTS
	IL ROUTE 78	
1	Rt. Sta. 909 + 19.95	SN 098-0118
1	Lt. Sta. 909 + 19.95	SN 098-0118
2	TOTAL	

**61000115 TYPE E INLET BOX STANDARD 610001**

EACH	LOCATION	COMMENTS
	IL ROUTE 78	
1	Rt. Sta. 909 + 19.95	SN 098-0118
1	Lt. Sta. 909 + 19.95	SN 098-0118
2	TOTAL	

**61100500 EXPLORATION TRENCH 52" DEPTH**

FOOT	LOCATION
20	Contingency
20	TOTAL

**61133200 FIELD TILE JUNCTION VAULTS 3' DIA.**

EACH	LOCATION
1	Contingency
1	TOTAL

**63000001 STEEL PLATE BEAM GUARDRAIL TYPE A 6 FOOT POSTS**

FOOT	LOCATION	COMMENTS
	IL ROUTE 78	
50	Rt. Sta. 908 + 68.1 - 909 + 18.1	SN 098-0118
12.5	Lt. Sta. 908 + 79.8 - 908 + 92.3	SN 098-0118
12.5	Rt. Sta. 911 + 26.6 - 911 + 39.1	SN 098-0118
50	Lt. Sta. 911 + 30.5 - 911 + 80.5	SN 098-0118
125	TOTAL	