150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

630
625
620

EXISTING FENCE
EXISTING ROW
622.57/57.41' LT
621.78/53.93' LT
1:3
625.28/40.67' LT
1.50%
625.43/30.67' LT
625.80/26.06' LT
4%
626.36/12.00' L
1.50 %
626.54
1.50 %
626.35/12.56' R
4% *
626.03/20.56' RT
1:4
620.70/46.41' RT
620.70/50.09' RT
EXISTING ROW

* SEE PRE-STAGE 1A STAGING DETAILS FOR SHOULDER LOCATIONS

C=24.1 F=49.6

912+50.00

EXISTING FENCE
EXISTING ROW
622.75/59.35' LT
621.70/55.20' LT
1:3
625.75/40.17' LT
1.50 %
625.90/30.19' LT
626.12/27.40' LT
4%
626.74/12.00' LT
1.50 %
626.92
1.50 %
626.73/12.38' RT
4% *
626.41/20.38' RT
1:4
620.64/47.79' RT
620.64/51.27' RT
EXISTING ROW

* SEE PRE-STAGE 1A STAGING DETAILS FOR SHOULDER LOCATIONS

C=21.1 F=62.7

SPECIAL DITCH
LT STA 912+25 - 915+50
621.70 - 622.68
SLOPE= 0.30%

912+25.00

EXISTING FENCE
EXISTING ROW
622.76/57.93' LT
621.59/53.42' LT
1:3
626.33/36.32' L
1.50 %
626.48/26.24' L
4%
627.05/12.00'
1.50 %
627.23
1.50 %
627.05/12.23'
4% *
626.52/25.21' R
1:4
620.58/50.82' RT
EXISTING ROW

* SEE PRE-STAGE 1A STAGING DETAILS FOR SHOULDER LOCATIONS

C=24.5 F=68.4

912+00.00

*IL 78

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

FINAL SURVEY
NOTE BOOK
NO.
SURVEYED BY
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
DATE

ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED BY
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
DATE

FILE NAME = c:\pw_work\pwidot\fasslermj\d0149594\D208209-sht-xssht_IL78.dgn	USER NAME = Fasslermj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Fri Jun 13 13:44:50 2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 78
MAINLINE CROSS SECTIONS

SCALE: | SHEET OF SHEETS | STA. 912+00.00 | TO STA. 912+50.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•22	15BR-1	WHITESIDE	146	134
		CONTRACT NO. 64F19		
	ILLINOIS FED. AID PROJECT			