

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|---------------------|--|-----------------|----------------|-------------------|-----------------|
| | | | | 100% STATE | 100% STATE |
| | | | | 0005 | 0005 |
| | | | | PEORIA | STARK |
| | | | | RURAL | RURAL |
| 40600285 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | LB | 78957 | 54204 | 24753 |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 2825 | 1970 | 855 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 0.67 | 0.33 |
| 40600982 | HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 3069 | 2302 | 767 |
| 40600990 | TEMPORARY RAMP | SO YD | 482 | 352 | 130 |
| 40603335 | HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 6624 | 4477 | 2147 |
| 40800050 | INCIDENTAL HOT - MIX ASPHALT SURFACING | TON | 93 | 71 | 22 |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SO FT | 3330 | 3330 | |
| 42400800 | DETECTABLE WARNINGS | SO FT | 401 | 401 | |
| 44000152 | HOT - MIX ASPHALT SURFACE REMOVAL, 3/4" | SO YD | 47418 | 28250 | 19168 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 405 | 405 | |
| 44000600 | SIDEWALK REMOVAL | SO FT | 3155 | 3155 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1149 | 643 | 506 |
| 60236800 | INLETS, TYPE A, TYPE 11 FRAME AND GRATE | EACH | 1 | 1 | |

13

FILE NAME =
Cover_GN_Line Diagram_Typicals.dgn

USER NAME = aubreygo
PLOT SCALE = 20.0000 / in.
PLOT DATE = 5/13/2014

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|------------|--------------|--------------|--------------------|
| 1375 | (8,10)RS-4 | PEORIA/STARK | 33 | 4 |
| | | | | CONTRACT NO. 68A95 |
| ILLINOIS FED. AID PROJECT | | | | |